

**Secondary School Site  
Search Report**

On behalf of Hertfordshire  
County Council

August 2021 (Rev 1)

Prepared by  
Vincent and Goring



# SECONDARY SCHOOL SITE SEARCH REPORT:

## BOREHAMWOOD

### Contents

|     |                         |    |
|-----|-------------------------|----|
| 1.0 | INTRODUCTION            | 2  |
| 2.0 | SITE SEARCH METHODOLOGY | 3  |
| 3.0 | BOREHAMWOOD SITE SEARCH | 8  |
| 4.0 | SUMMARY AND CONCLUSION  | 16 |

### Appendix 1: Education need

2020/21 Summer forecast – secondary

### Appendix 2: Planning appraisal

Proforma template for planning appraisal

### Appendix 3: Settlement site search plans

5309/300/C Urban area site search plan

5309/301/C Non-urban area site search plan

### Appendix 4: Planning appraisals

Borehamwood 01

Borehamwood 02 (and Transport Appraisal)

Borehamwood 03 (and Transport Appraisal)

Borehamwood 04 (and Transport Appraisal)

Borehamwood 05 (and Transport Appraisal)

Borehamwood 06

Borehamwood 07 (and Transport Appraisal)

Borehamwood 08 (and Transport Appraisal)

### Appendix 5: Transport Appraisals ranking



## 1.0 INTRODUCTION

- 1.1 Vincent and Gorbing have been commissioned by Hertfordshire County Council (HCC) to undertake a search for potential secondary school sites in south-west Hertfordshire in response to confirmed secondary education need arising from potential housing and demographic growth identified during the current preparation of new local plans.
- 1.2 HCC is working with local planning authorities to ensure that a robust infrastructure strategy is in place for the delivery of new secondary schools where they may be required. It is understood that the site search will help to inform the early stages of plan preparation to identify suitable sites that could be allocated for secondary school use. It is acknowledged that sites identified for education purposes may be suitable for other uses. For example, a site that is suitable for residential development may or may not be suitable for education use. A site suitable for education use may or may not be suitable for residential development. Some sites may be suitable for both uses. The decision as to which sites should be allocated for residential development and which for education use is a matter for the local planning authority based on the evidence available. It is for the local planning authority to resolve competing interests, to liaise with all stakeholders and to ensure the infrastructure needs of the district are fully met in emerging local plans.
- 1.3 NPPF 2021 (para 15) is clear that up to date plans should “provide a positive vision for the future of each area; a framework for addressing housing needs and other economic, social and environmental priorities” including strategic priorities for education (para 20 c). It is made clear in para 24 that “local planning authorities and county councils (in two tier areas) are under a duty to cooperate with each other”. In relation to education need NPPF (para 95) states that “it is important that a sufficient choice of school places is available to meet the needs of existing and new communities. Local planning authorities should take a proactive, positive, and collaborative approach to meeting this requirement, and to development that will widen choice in education. They should: give great weight to the need to create, expand or alter schools through the preparation of plans...” Therefore, NPPF emphasises the need to ensure that where an education need is identified in communities it is fully met in local plans.
- 1.4 HCC has identified a need for one 8fe secondary school site to serve potential housing and demographic growth in Borehamwood. This report sets out the conclusions of the site search for this area. It does not detail or justify the education need requirement, that is a matter for HCC. Neither does it seek to make judgements about the proximity of potential school sites in relation to existing school sites. That is a matter for HCC. In parallel a separate secondary school site search report has been prepared for south-east Watford and Bushey.
- 1.5 Section two sets out the methodology used for identifying potential secondary school sites of the appropriate size and suitability. This methodology is common to all site search areas.
- 1.6 Section three presents the outcomes for the Borehamwood site search. Site visits were undertaken in July 2020.
- 1.7 Section four comprises the summary and conclusion.

## 2.0 SITE SEARCH METHODOLOGY

- 2.1 This section of the report sets out: the projected need for a new secondary school in Borehamwood; the required site size and site characteristics for a 8fe secondary school; the sequential site search methodology used for searching for a site firstly in the urban area and then secondly in the non-urban area; and, finally the process for individual site analysis followed by site ranking.

### EDUCATION NEED

- 2.2 HCC has several statutory duties in relation to the provision of additional school places, namely:
- Promoting high standards of education and fair access to education
  - Planning and commissioning school places in its area
  - Extending diversity and choice
  - Co-ordinating admissions for all maintained schools and academies in the normal admission round
  - Resourcing shared maintenance, improvement to and provision of the built environment and securing value for money
- 2.3 The role of HCC in ensuring sufficient supply of suitable school places is that of a commissioner rather than as a direct provider of school places. HCC has a duty to secure sufficient school places in its area and to allocate those places to the children of all parents who want one.
- 2.4 HCC fulfils these planning responsibilities by forecasting the demand for school places to ensure sufficient school places are available to meet demand within mainstream schools. It negotiates the right number of places on an annual basis and undertakes longer term strategic planning.
- 2.5 HCC produces local forecasts of the demand for secondary school places to anticipate a shortfall or surplus of places by (Education) Planning Areas. Pupil numbers are forecast considering:
- Historic pupil numbers in each school year group
  - 0-5-year old children registered with general practitioners
  - Primary pupils moving on to secondary school
  - Additional pupils arising from new housing developments
  - Pupil movement patterns taking account of cross area flows both within planning areas within Hertfordshire and out of the county as well as from the independent sector
- 2.6 Secondary school forecasts are based on actual children, both in schools and registered with general practitioners for 10 years ahead together with a calculation of additional pupils arising from new housing developments.

- 2.7 The HCC summer forecast (2020/21) for secondary school places is attached at Appendix 1. The forecast shows that for Borehamwood there is a deficit of places across the plan period from 2025-26 – 2029-30. This deficit underpins a requirement for a secondary school site to be delivered early in the plan period. HCC have identified that this requirement can be met through the provision of a new 8fe<sup>1</sup> secondary school in Borehamwood.

## SITE SIZE AND BUILDING SIZE

- 2.8 School standards have recently changed (School Premises Regulations 2012) and provide a much less stringent approach to school standards. HCC has previously agreed to use the site areas that refer to Building bulleting 103 for primary and secondary guidance as these are deemed a suitable standard for school premises.

| Table 1: Site size areas for secondary schools: BB103 compliance |              |               |  |
|--|--------------|---------------|--|
| 6fe (ha)   | 8fe (ha)     | 10fe (ha)     | Category/Comments  |
| >8.36  | >10.78       | >13.20        | Preferred – should allow a fully BB103 compliant school to be built on the site, including where there are minor abnormal features or constraints.                   |
| 6.66 – 8.36  | 8.58 – 10.78 | 10.50 – 13.20 | Sub-optimal – may allow a fully BB103 compliant school, subject to any constraints or abnormal features which reduce the developable/usable area. May require a DPF. |
| <6.66  | <8.58        | <10.50        | Would not normally be considered. Should be included in the 'long list' in case they would be viable as detached playing fields (dpf) or as 'split site' solutions.  |

- 2.9 The site size requirements set out in Table 1 above indicate that for a **8fe** school there is a preference for a site to be more than **10.78ha** which will allow for any potential abnormal site constraints. Should there be no suitable sites of more than **10.78ha** then a site of between **8.58ha-10.78ha** could be identified but this would be sub-optimal. Sites of under **8.58ha** would not normally be considered but could be part of a split site solution.
- 2.10 So, the preference for the Borehamwood site search is to identify a **10.78ha >** site which would include a building zone of **3.56ha**. Should a suitable site of this size not be identified then a sub-optimal site of between **8.58ha-10.78ha** could be identified.

<sup>1</sup> School provision is often described in terms of "forms of entry". 1 form of entry (fe) equals 30 places per year group. Secondary schools have five-year groups from Year 7 through to Year 11 and Sixth forms with lower and upper year groups.

- 2.11 Ideally an 8fe secondary school should have all the facilities it requires, including playing fields provided on a single site. There may, however, be situations where a split site is identified as preferential. In this circumstance the site size for a school building zone would be slightly higher because more facilities would be needed in the school buildings location to account for a detached school playing field. In this scenario for an **8fe** secondary school a school building zone of **4.38ha** is required and a playing field of **6.4ha** would be required making up the total site area of **10.78ha**. In the event of a split site scenario there would need to be no more than **400m walking distance** between the two sites to ensure that the detached playing field could be easily accessed during the school day for curriculum use.
- 2.12 The building zone of any secondary school site needs to be able to accommodate a minimum footprint which is generated from the number of pupils attending the school (based again on school size).

| Table 2: Building footprint: BB103 compliance |               |                           |
|---|---------------|---------------------------|
| School size                                   | No. of pupils | Gross area m <sup>2</sup> |
| 6fe   | 1152          | 9,023                     |
| 8fe   | 1535          | 11,557                    |
| 10fe  | 1920          | 14,014                    |

- 2.13 Table 2 above shows the building footprint requirements for each size of school which assumes a typical curriculum, standard labs, hall with bleacher seating, 60- minute dining including school hall, 70% staying on rate and classrooms at HCC standard size. These footprint requirements are utilised when a site is identified as preferential and development principles plans are being prepared which shows the extent of the building zone the extent of playing fields and, how the site can be accessed.

## SEQUENTIAL SITE SEARCH METHODOLOGY

### Study area mapping

- 2.14 The site search begins with the identification of the study area which is mapped onto an Ordnance Survey base. The broad study area is based on the secondary education planning area in which the education need is identified. The study area boundary is then identified using natural boundaries (e.g., roads/railways/administrative boundaries). As part of the interim meeting held with the local planning authority the study area boundary is explained, discussed, and agreed. Adjustments to the study area boundary may be made after the interim meeting with the local planning authority.
- 2.15 The local planning authority can supply local information on sites being promoted which can be added to the study area mapping. Some of the sites being promoted for other uses (e.g., residential development) may also be suitable for education use. It is for the local planning authority to assess and weigh the education need alongside other needs and to plan accordingly in line with Government advice.

## Urban area site search

- 2.16 Once the study area is agreed then the sequential site search commences. The sequential site search is a two-stage process: firstly, an urban area site search and secondly a non-urban area site search if the urban area site search does not yield any suitable sites.
- 2.17 The urban area site search begins with a mapping of all HCC owned land, playing fields and open spaces, open land, allotments, and employment areas. Sites that might be released for development as part of any local plan review are also mapped within the urban area.
- 2.18 Once this mapping is completed each of the sites identified is measured to determine whether it falls within the site size range, in this case **8.58ha-10.78ha** or whether there are smaller sites of **4.38ha** with sites for a detached playing field of **6.4ha** within a **400m walking distance**. A radius of 400m walking distance is applied to the mapping where sites are **4.38ha** or more. HCC considers it is reasonable in any split site search to identify sites which collectively deliver the preferred site size rather than a sub-optimal solution.
- 2.19 If there are sites that are more than **4.38ha** with another site of **6.4ha** within a 400m walking distance, then the sites are taken forward for further consideration.

## Non-urban area site search

- 2.20 The non-urban site search begins with a mapping of all the potential environmental constraints where these exist around the settlement boundaries. These constraints fall into two categories: category 1 constraints that preclude development and category 2 constraints that may hinder development. Category 1 constraints comprise: woodland areas, conservation areas, parks/gardens, Scheduled Ancient Monuments, Areas of Outstanding Natural Beauty (AONB), active golf courses (unless identified as potential future housing sites), landscape designations, landscape conservation areas, sites of special scientific interest (SSSI), nature reserves, wildlife sites, environmental agency designated flood zones 2 and 3 (where the majority of the site is covered by this designation). Sites in these locations are not considered suitable for development.
- 2.21 Category 2 constraints include: areas of archaeological interest (as development mitigation might be sought prior to development), noise sources (which could be mitigated through noise attenuation measures), playing fields (as these might not be in active use), and designated public footpaths, restricted byways and bridleways which may possibly be diverted or may pose a constraint to the way in which the site is developed. These constraints may not necessarily preclude development on the site.
- 2.22 It should be noted that this methodology does not entirely rule out development constraints since until detailed site investigations are completed, site constraints are not always fully known. It does however provide an initial site sieving mechanism to identify the sites with the best prospect for secondary school use.
- 2.23 Sites within areas identified by local planning authorities as potential areas of growth were also mapped onto the non-urban area plans. It was agreed with the County Council and in meetings with the local planning authorities that these potential areas of growth could alternatively accommodate secondary school sites along with other uses if the site-specific criteria above could be met.
- 2.24 Hertsmere Borough Council supplied the HELAA sites which were added to the mapping for both urban and non-urban areas.

## Site identification

- 2.25 Once Category 1 and 2 constraints are mapped, a short list of sites outside of the urban area of more than **8.58ha** (ideally more than **10.78ha**) is prepared excluding any category 1 constraints areas (as set out above). Sites are identified where they: adjoin the urban area or settlement boundary, and adjoin a road (A road, B road and minor road).
- 2.26 These basic requirements are needed to ensure the site is sustainable: within walking distance of the existing population and/or any proposed expansion that vehicular access can be achieved, and that there is minimum encroachment into the Green Belt. If there are Category 2 constraints a larger site area may need to be identified to ensure there is flexibility to deliver the school should those constraints affect development potential.

## Site analysis

- 2.27 Once the shortlisted sites are identified a planning appraisal is undertaken using a proforma which captures the same information for each site. The proforma includes a standard list of positive and negative site attributes which are applied to all sites to enable a consistent approach to the appraisal. The planning appraisal includes a site visit to assess the site and a record of the site visit is taken through site photographs. This is to ensure that all matters are fully considered on each site. The proforma template is attached at Appendix 2.
- 2.28 Following the initial site visit and planning appraisal some sites may be rejected if it is considered that the site is unlikely to be suitable for development. These reasons are set out in the conclusion to the planning appraisal for each site.
- 2.29 Following the completion of the initial site visit and planning appraisal those sites that are not rejected are proposed for a high-level transport appraisal. The high-level transport appraisal examines site compliance to LTP4 (Local Transport Plan) policies, means of access appraisal (to confirm the initial planning appraisal), and an assessment of the local highway network. This highways appraisal is undertaken by Civil Engineering Consultants Stomor Ltd. and prepared in consultation with HCC Highways.
- 2.30 Sites may then be rejected following transport appraisal if there is no suitable and safe means of access or if sustainable transport modes cannot be achieved.
- 2.31 It should be noted that all transport appraisals contained in this report were prepared during the period of the Covid-19 pandemic. Therefore, traffic conditions at the time of writing do not reflect former 'typical' traffic condition and as such it is not possible to comment upon existing highway conditions in terms of congestion in the vicinity of the sites. Further work would be required when traffic levels return to their pre-Covid-19 levels.

## Site ranking

- 2.32 The final list of potential sites is then ranked according to their planning and highways appraisal performance and a recommendation is made.

### 3.0 BOREHAMWOOD SITE SEARCH

- 3.1 This section of the report presents the outcomes for the Borehamwood site search summarising the outcomes from the urban and non-urban site search, and the identification of a preferred site(s).

#### URBAN AREA SITE SEARCH

- 3.2 Plan 5309/300/C (attached at Appendix 3) sets out the mapping of sites in the urban area. The study area boundary was discussed at a meeting with Hertsmere Borough Council on 1 July 2020. The boundary of the study area is defined by field boundaries and minor roads to the north, the A1 to the east, the A411, administrative and field boundaries to the south, and Watling Street to the west.
- 3.3 Plan 5309/300/C identifies: HCC ownership (14 sites), playing fields and play spaces (11 sites), areas of open land (11 sites), allotments (1 site), employment areas (3 sites). All the sites are listed in the key together with the site areas. Those sites in the key listed as being below 4.38ha were rejected.
- 3.4 The following sites exceeded the site size requirement for a split site with a detached playing field of **4.38ha** and so were evaluated as set out below:
- PF3 Aycliffe Park 5.41ha – there are no sites within 400m walking distance of this site, the closest is PF4 which is just outside the 400m walking distance
  - PF4 Aberford Park 6.51ha – PF6 is within 400m walking distance of this site but PF6 currently accommodates Borehamwood FC and this site is not available
  - PF6 Meadow Park 8.78ha – this site currently accommodates Borehamwood FC and is not available
  - OL9 Denham Way 4.73ha- whilst this site is, in overall site area large enough, it is fragmented and would not provide sufficiently large collective site areas for playing fields or building zone
  - E1 Television Studios 6.29ha – this employment site is in active use and there are no sufficiently large site areas at the present time which would be suitable for future use
  - E2 Elstree Way 34.49ha - this employment site is in active use and there are no sufficiently large site areas at the present time which would be suitable for future use
  - E3 Sterling Way 7.09ha - this employment site is in active use and there are no sufficiently large site areas at the present time which would be suitable for future use
- 3.5 It was therefore concluded that there are no available suitable sites within the urban area of over **4.38ha** which would provide a site for a school building zone with detached playing fields within a 400m walking distance.

## NON- URBAN AREA SITE SEARCH

### Site identification

- 3.6 Plan 5309/301/C (attached at Appendix 3) sets out the mapping of environmental constraints outside the urban area adjoining the settlement boundary of Borehamwood. The mapping shows that large areas of land to the north, south and west of Borehamwood (adjoining the settlement) are designated wildlife sites and so these areas of land are excluded from the site search. This leaves land adjoining the east of the settlement (excluding the wooded belt east of the B5378) and land to the south-west of the settlement.
- 3.7 Following the mapping of environmental constraints the following potential secondary school sites were shortlisted as being of more than 8.58ha:
- Bore 01: Land west of A1(M)
  - Bore 02: Land north of Rowley Lane
  - Bore 03: Land east of Green Street (Parcel A)
  - Bore 04: Land east of Green Street (Parcel B)
  - Bore 05: Land east of Green Street (Parcel C)
  - Bore 06: Land north of Allum Lane
  - Bore 07: Land south of Allum Lane
  - Bore 08: Land south of A411

### Site analysis

Town planning appraisals of all these sites were undertaken and are attached at Appendix 4. Some sites were taken forward for transport appraisals. Conclusions of the planning and where appropriate transport appraisal are summarised below.

#### Bore 01: Land west of A1(M)

- 3.8 The site is located on land west of the A1(M) and east of Rowley Lane (plan 5309/301/C). The existing use is a car/lorry park. The site is in single ownership and almost entirely level. The site is an optimal size for an 8fe school. Upon further investigation the site is unlikely to be available. Planning permission has been granted for the development of Sky Studios Elstree, a TV and film studio expected to be open in 2022. This site was not recommended for high level transport appraisal or for comparative assessment with other sites.



**Bore 02: Land north of Rowley Lane**

- 3.9 The site is located north of Rowley Lane and east of Well End Road (plan 5309/301/C). The existing use is agricultural. The site is in single ownership and is predominantly flat with a very gentle incline from east to west. The site is well enclosed by existing vegetation from all directions. The site is an optimal size for an 8fe school. The site was recommended for transport appraisal.
- 3.10 The conclusions of the high -level transport appraisal was that there are some reservations on the suitability of increased vehicle movements along the rural section of Rowley Lane and the access onto the A1 from Holmshill Lane. A detailed review of the potential impact of school related traffic along these roads will need to be undertaken and significant improvements to the road layout will be required in order to provide a safe and suitable route, or alternatively, measures to discourage school related travel along this route. There are also potential capacity issues along Potters Lane for vehicles and cyclists, which is likely to be on a key desire line from the northern side of Borehamwood. If the concerns identified above can be mitigated to a suitable standard, then, in principle, the site may be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment. Footways along residential roads to the west and south-west of the site are generally considered suitable. However, new crossing facilities are likely to be required. Bus accessibility to the site from Borehamwood and Elstree is reasonable, with bus stops on Alexandra Road providing access to route B3. However, existing links to the wider area would be from stops available on the B5378 Shenley Road and the A5135 Elstree Way which are over 1km from the school site. Improved accessibility between the site and the local bus stops should be considered as part of proposals. Overall, the site was ranked lowest (6/6) in terms of access and highways suitability. It scored least well of all the sites in terms of providing a safe and suitable vehicular access, its location and proximity to accessible sustainable transport modes, and anticipated mitigation works.
- 3.11 A development principles plan (5309/322) has been prepared and is attached at Appendix 3. This plan shows the disposition of the building zone, playing fields and the optimal point of access for the site (based on highway conclusions). The most suitable point of access would be from Well End Road, preferably towards the southern end so as to discourage the number of vehicles travelling via Potters Lane, although a suitable distance from the Rowley Lane junction should be allowed. The location of an access from Well End Road would likely impact on an existing ditch, trees and hedgerows and would be directly opposite residential driveways. Visibility in both directions along Well End Road may require removal of hedgerow and trees, subject to further survey.
- 3.12 It is concluded that because of the highway concerns relating to the suitability of the surrounding highway infrastructure for a school development, lack of nearby public transport infrastructure and the limited potential for highway improvements, this site should not be considered for an 8fe school unless another more sequentially preferable site cannot be identified.

**Bore 03: Land east of Green Street (Parcel A)**

- 3.13 The site is located east of Green Street, Borehamwood (plan 5309/301/C) extending north-east away from Green Street. The existing use is agricultural. The site is in single ownership and is flat. The site is an optimal size for an 8fe secondary school. The site was recommended for transport appraisal.

- 3.14 The conclusions of the transport appraisal were that: in principle, it would appear that the road network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment. It is suggested that adequate pedestrian crossings are provided along Green Street and at suitable locations within the residential area to the south-west, in order to provide a safe and suitable route for pupils to access the school. The footway network along residential roads to the south-west of the site is generally considered suitable. Bus services in the vicinity of the site appear to be infrequent. Therefore, additional services may be required to ensure that bus access to the site is feasible. Overall, the site was ranked 4/6 in terms of access and highways suitability. Whilst it scored high on providing a safe and suitable vehicular access, it scored less favourably in terms of its location and access by sustainable forms of transportation.
- 3.15 A development principles plan (5309/332) has been prepared and is attached at Appendix 3. The plan shows the disposition of the building zone, playing fields and the optimal point of vehicular access to the site (based on transport appraisal conclusions). The tree line in the centre of the site splitting the 2 land parcels could be retained although there would be poor supervision and intervisibility between the school building and the playing fields.
- 3.16 It is concluded that that because poor intervisibility between the school building zone and the playing fields and the comparatively undesirable location of the site in terms of its access by sustainable forms of transport, this site should not be considered for an 8fe school unless another more sequentially preferable site cannot be identified.

#### **Bore 04: Land east of Green Street (Parcel B)**

- 3.17 The site is located east of Green Street, Borehamwood (plan 5309/301/C) extending north-west in parallel to Green Street. The existing use is agricultural, and the site is in 3 ownerships. The site is an optimal size for an 8fe secondary school. The site was recommended for transport appraisal.
- 3.18 The conclusions of the high-level transport appraisal were that: in principle, it would appear that the road network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment. It is suggested that adequate pedestrian crossings are provided along Green Street and at suitable locations within the residential area to the south-west, in order to provide a safe and suitable route for pupils to access the school. The footway network along residential roads to the south-west of the site is generally considered suitable. Bus services in the vicinity of the site appear to be infrequent. Therefore, additional services may be required to ensure that bus access to the site is feasible. Overall, the site was ranked 3/6 in terms of access and highways suitability. Whilst it scored high on providing a safe and suitable vehicular access, it scored less favourably in terms of its location and access by sustainable forms of transportation.
- 3.19 A development principles plan (5309/342) has been prepared and is attached at Appendix 3. The plan shows the disposition of the building zone, playing fields and the optimal point of vehicular access to the site (based on transport appraisal conclusions). The location of the playing fields would require the removal of a significant tree belt in the centre of the site.
- 3.20 It is concluded that because of the need to remove mature vegetation on site and the comparatively undesirable location of the site in terms of its access by sustainable forms of transport, this site should not be considered for an 8fe school unless another more sequentially preferable site cannot be identified.

**Bore 05: Land east of Green Street (Parcel C)**

- 3.21 The site is located east of Green Street, Borehamwood (plan 5309/301/C) extending north-east away from Green Street. The existing use is agricultural, and the site is in 3 ownerships. The site was recommended for transport appraisal.
- 3.22 The conclusions of the transport appraisal were that: in principle, it would appear that the road network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment. It is suggested that adequate pedestrian crossings are provided along Green Street and at suitable locations within the residential area to the south-west, in order to provide a safe and suitable route for pupils to access the school. The footway network along residential roads to the south-west of the site is generally considered suitable. Bus services in the vicinity of the site appear to be infrequent. Therefore, additional services may be required to ensure that bus access to the site is feasible. The site was ranked 5/6 in terms of access and highways suitability. Whilst it scored high on providing a safe and suitable vehicular access, it scored less favourably in terms of its location and access by sustainable forms of transportation and issues with parking on Green Street.
- 3.23 A development principles plan (5309/352) has been prepared and is attached at Appendix 3. The plan shows the disposition of the building zone, playing fields and the optimal point of vehicular access to the site (based on transport appraisal conclusions). The playing fields would be split into two parcels unless the tree line between them is removed. The tree lines around the building zone boundaries to the playing fields could be retained although there would be poor supervision and intervisibility between the school building and the playing fields.
- 3.24 It is concluded that because of the need to remove mature vegetation on site, the poor supervision and intervisibility between the building zone and the playing fields and the relatively undesirable location of the site in terms of its access by sustainable forms of transportation, this site should not be considered for an 8fe school unless another more sequentially preferable site cannot be identified.

**Bore 06: Land north of Allum Lane**

- 3.25 The site is located north of Allum Lane, Borehamwood (plan 5309/301/C). The existing uses are grassland and part of Radlett Park Golf Club which is identified as site HEL514 in the HELAA 2019 Report. The site is in 2 ownerships. The site is an optimal size for an 8fe secondary school.
- 3.26 The site is moderately sloped, inclining to the east meaning which would necessitate some regrading. Site development may be exposed to long distance views in the wider landscape. There is a significant area of large mature trees within the site that would require removal to accommodate the development. Part of the site is in an area of archaeological importance adding a further potential constraint. Whilst the site is in the HELLA as a potential housing site it was found to be still in use as a golf course.
- 3.27 For the above reasons, the site was too heavily constrained and was not therefore recommended for a transport appraisal or for comparative assessment with other sites.

### Bore 07: Land south of Allum Lane

The site is located south of Allum Lane, Borehamwood (plan 5309/301/C). The existing use is agricultural pastureland. The site is in 3 ownerships. The site is an optimal size for an 8fe secondary school.

- 3.28 Although the site is undulating with a gentle slope upwards towards the centre of the site and downwards on either side to the east and west it is relatively enclosed, and the site is known to be available. There are two potential points of access from The Rise or Allum Lane which could potentially be utilised. The site was recommended for a transport appraisal.
- 3.29 The conclusions of the transport appraisal were that: in principle, it would appear that the road network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment. The current width of Allum Lane is considered sufficient for the amount of traffic present as well as an additional access for a school. However, the access location and associated impact on the B5378 Allum Lane would need to be carefully considered in order to minimise the impact on the free flow of traffic along the road while also providing a suitable access arrangement for the school site. It is suggested that adequate pedestrian crossings are provided along Allum Lane and at suitable locations within the residential area to the east, in order to provide a safe and suitable route for pupils to access the school. The footway network along residential roads to the east and north-east of the site is generally considered suitable. Bus accessibility to the site from Borehamwood and Elstree is reasonable, with bus stops on the B5378 Allum Lane. Improved accessibility between the site and the local bus stops should be considered as part of proposals. Overall, the site was ranked 2/6 in terms of highways and access.
- 3.30 Two development principles plans (5309/372 and 5309/373) have been prepared and are attached at Appendix 3.
- 3.31 Plan 5309/372 shows the retention of the possible housing allocation (hatched) with a school building zone to the south accessed from The Rise and playing fields to the west of the site. The location of the school would necessitate the diversion of a footpath along the tree line boundary (as shown), locating the playing fields on significantly undulating land (particularly the farthest western parcel) requiring significant re-grading and the use of The Rise which, at this stage has been identified in the transport appraisal as a sub-optimal access solution. Overall, the site area for the school would be slightly sub-optimal being 10.54ha which is just below the 10.78ha requirement for an 8fe secondary school.
- 3.32 Plan 5309/373 shows the removal of the possible housing allocation with a school building zone to the north accessed from Allum Lane and the playing fields to the south of the school building zone. The location of the school would not necessarily require the diversion of the footpath if a secure line through the playing field could be established with the use of fencing. However, the footpath could be diverted if required along the tree line as shown on plan 5309/392. This site arrangement would not require the farthest western parcel of the site thus reducing potential re-grading requirements. This option proposes the use of Allum Lane which at this stage has been identified in the transport appraisal as the preferred access solution. There may be a requirement for a landscape buffer to manage the relationship between the building zone and adjoining residential dwellings on the eastern site boundary. Overall, the site area for the school would be 12.58ha which is above the 10.78ha requirement for an 8fe secondary school.
- 3.33 At this stage, given the constraints currently identified (including regrading) the preferred land use option would be the development principles layout shown on plan 5309/373.

- 3.34 The site it is concluded would be suitable for an 8fe secondary school subject to further technical and environmental investigations.

#### Bore 08: Land south of A411 (Barnet Lane)

- 3.35 The site is located south of A411 (Barnet Lane), Borehamwood (plan 5309/301/C). The existing use is agricultural. The site is in single ownership. The site is an optimal size for an 8fe secondary school. The site is an optimal size for an 8fe secondary school site. The site lies part in the administrative borough of Hertsmere and part in the administrative borough of Barnet. The site is almost entirely level. The site was recommended for a transport appraisal.
- 3.36 The conclusions of the transport appraisal were that: in principle, it would appear that the road network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment. Although the Highway Authority usually resists new accesses onto 'A' roads, the A411 Barnet Lane to the west of Furzehill Road appears to be a suitable location for a school access to be established, provided an acceptable junction arrangement can be achieved. There may be potential for park and stride arrangements from nearby car parks associated with Morrisons and other commercial properties on Stirling Way, which would help to discourage travel by car and avoid provision of parent drop off facilities on site. The local footway and cycleway network appear to be generally good and suitable for school related movements. However, upgraded crossing facilities will be required, particularly on the A411 Barnet Lane. It is recommended that measures to manage traffic speed would be required in the vicinity of the school such as a reduction in speed limit to 30mph in the immediate vicinity of the site. Bus accessibility to the site is considered good, with bus stops adjacent to the site and within close proximity. Access between the site and the local bus stops should be considered as part of the proposals. Overall, the site was ranked 1/6 (receiving the top ranking) when compared with other sites.
- 3.37 A development principles plan (5309/382) has been prepared and is attached at Appendix 3. The plan shows the disposition of the building zone, playing fields and the optimal point of vehicular access to the site (based on transport appraisal conclusions). The highways appraisal identified 2 potential points of access from Barnet Lane to the east and west of the roundabout adjoining the site. The eastern point of access has been identified to allow for the building zone to be located away from the area of potential high-risk surface water flooding at the eastern part of the site. The playing fields may impact on a tree line running east west through the site but depending on layout the tree line may be retained. Some vegetation along the site frontage and scattered trees may require removal.
- 3.38 The site it is concluded would be suitable for an 8fe secondary school subject to further technical and environmental investigations.

#### Site ranking

- 3.39 Eight potential secondary school sites were initially identified in Borehamwood:
- Bore 01: Land west of A1(M)
  - Bore 02: Land north of Rowley Lane
  - Bore 03: Land east of Green Street (parcel A)
  - Bore 04: Land east of Green Street (parcel B)
  - Bore 05: Land east of Green Street (parcel C)
  - Bore 06: Land north of Allum Lane

- Bore 07: Land south of Allum Lane
  - Bore 08: Land south of A411(Barnet Lane)
- 3.40 Initial planning appraisals were completed on eight sites which concluded in two sites being rejected: Bore 01 Land west of A1(M) and Bore 06 Land north of Allum Lane.
- 3.41 High level transport appraisals were undertaken on the remaining 6 sites.
- Bore 02: Land north of Rowley Lane
  - Bore 03: Land east of Green Street (parcel A)
  - Bore 04: Land east of Green Street (parcel B)
  - Bore 05: Land east of Green Street (parcel C)
  - Bore 07: Land south of Allum Lane
  - Bore 08: Land south of A411(Barnet Lane)
- 3.42 None of the sites were found to be unsuitable, in transport terms for an 8fe secondary school (subject to further analysis in a post COVID situation).
- 3.43 Development principles plans were then prepared for the 6 sites which demonstrated where access could be taken (using the transport appraisals) and consequently where building zones and playing fields might be located.
- 3.44 As a consequence of the transport concerns relating to the suitability of the surrounding highway infrastructure for a school development, lack of nearby public transport infrastructure and the limited potential for highway improvements, it was concluded that Bore 02 Land north of Rowley Lane should not be considered for an 8fe school unless another more sequentially preferable site cannot be identified.
- 3.45 As a consequence of poor intervisibility and supervision between the school building zone and the playing fields and the comparatively undesirable location of the site in terms of its access by sustainable forms of transport, it was concluded that Bore 03 Land east of Green Street (parcel A) should not be considered for an 8fe school unless another more sequentially preferable site cannot be identified.
- 3.46 As a consequence of the need to remove mature vegetation on site and the comparatively undesirable location of the site in terms of its access by sustainable forms of transport, it was concluded that Bore 04 Land east of Green Street (parcel B) should not be considered for an 8fe school unless another more sequentially preferable site cannot be identified.
- 3.47 As a consequence of the need to remove mature vegetation on site, the poor supervision and intervisibility between the building zone and the playing fields and the relatively undesirable location of the site in terms of its access by sustainable forms of transport, it was concluded that Bore 05 Land east of Green Street (parcel C) should not be considered for an 8fe school unless another more sequentially preferable site cannot be identified.
- 3.48 This leaves Bore 07 Land south of Allum Lane and Bore 08 Land south of London Road for further consideration. The high-level transport ranking appraisal at Appendix 5 ranks Bore 7 as second preferred and Bore 8 as first preferred. Further technical and environmental investigations are required to determine which of these sites is more sequentially suitable for development prior to a final recommendation.



## 4.0 SUMMARY AND CONCLUSION

- 4.1 A site search of the urban areas of Borehamwood resulted in no suitable or available sites being identified within the urban area. Consequently, the site search extended to the non-urban area searching for sites that adjoin the urban area.
- 4.2 Initially eight sites were identified. Planning appraisals were completed comprising a site visit, photographic appraisal, site appraisal and the completion of a proforma using the common template. Completion of the planning appraisals resulted in 6 sites being identified as suitable for further investigation.
- 4.3 A high-level transport appraisal was completed for Bore sites 02,03,04,05,07 and 08 which concluded that Bore 02, Bore 03, Bore 04 and Bore 05 were considered sub-optimal in transport terms. The high-level transport ranking appraisal ranked Bore 07 Land south of Allum Lane in second position and Bore 08 Land south of London Road in first position.
- 4.4 Development principles plans were prepared for each of the 6 sites. In addition to the sub-optimal transport status above Bore 03 and Bore 05 would have poor intervisibility and supervision between the school building zone and the playing fields and development of Bore 04 would necessitate the removal of mature vegetation on site as well as there being poor intervisibility and supervision between the building zone and the playing fields.
- 4.5 Consequently Bore 07 and Bore 08 remain for further investigation. Further comparative investigations would enable a more rigorous decision to be taken on which of these sites is more sequentially preferable to be allocated as an 8fe secondary school site.
- 4.6 Although further technical and environmental investigations would provide a more informed analysis of the site constraints for Bore 07 and Bore 08, it is ultimately a matter for the local planning authority to determine which site may be allocated for secondary education use, by resolving competing interests and liaising with all stakeholders (including HCC) to ensure the infrastructure needs of the district are fully met in the local plan.

## APPENDIX 1



## 2020/21 SUMMER FORECAST – SECONDARY

### Berkhamsted

| 18.0.0 Berkhamsted |  |                             |         |         |         |          |         |         |         |         |         |         |         |         |         |
|--------------------|--|-----------------------------|---------|---------|---------|----------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| School Code        | School Name                                | Places Available<br>2020-21 | Actuals |         |         | Forecast |         |         |         |         |         |         |         |         |         |
|                    |  |                             | 2017-18 | 2018-19 | 2019-20 | 2020-21  | 2021-22 | 2022-23 | 2023-24 | 2024-25 | 2025-26 | 2026-27 | 2027-28 | 2028-29 | 2029-30 |
| 5406               | Ashlyns School                             | 240                         | 239     | 244     | 242     |          |         |         |         |         |         |         |         |         |         |
|                    | Total Year 7 Pupil Demand                  |                             | 239     | 244     | 242     | 261      | 270     | 267     | 245     | 261     | 248     | 252     | 266     | 268     | 275     |
|                    | Total Year 7 Places Available              | 240                         |         |         |         | 240      | 240     | 240     | 240     | 240     | 240     | 240     | 240     | 240     | 240     |
|                    | Surplus or Shortage of Year 7 Places (No.) |                             |         |         |         | -21      | -30     | -27     | -5      | -21     | -8      | -12     | -26     | -28     | -35     |
|                    | Surplus or Shortage of Year 7 Places (%)   |                             |         |         |         | -8.8%    | -12.5%  | -11.3%  | -2.1%   | -8.8%   | -3.3%   | -5.0%   | -10.8%  | -11.7%  | -14.6%  |
|                    | Surplus or Shortage of Year 7 Places (FE)  |                             |         |         |         | -0.7     | -1.0    | -0.9    | -0.2    | -0.7    | -0.3    | -0.4    | -0.9    | -0.9    | -1.2    |

### Hemel Hempstead

| 19.0        | Hemel Hempstead                            |                             |         |         |         |          |         |         |         |         |         |         |         |         |         |
|-------------|--|-----------------------------|---------|---------|---------|----------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| School Code | School Name                                | Places Available<br>2020-21 | Actuals |         |         | Forecast |         |         |         |         |         |         |         |         |         |
|             |  |                             | 2017-18 | 2018-19 | 2019-20 | 2020-21  | 2021-22 | 2022-23 | 2023-24 | 2024-25 | 2025-26 | 2026-27 | 2027-28 | 2028-29 | 2029-30 |
| 4005        | The Hemel Hempstead School                 | 217                         | 186     | 186     | 218     |          |         |         |         |         |         |         |         |         |         |
| [4029]      | [Adeyfield School]                         | 0                           | 94      | 0       | 0       |          |         |         |         |         |         |         |         |         |         |
| 4032        | The Adeyfield Academy                      | 150                         | 0       | 117     | 113     |          |         |         |         |         |         |         |         |         |         |
| [4100]      | [The Cavendish School]                     | 0                           | 112     | 0       | 0       |          |         |         |         |         |         |         |         |         |         |
| 4033        | Laureate Academy                           | 210                         | 0       | 145     | 138     |          |         |         |         |         |         |         |         |         |         |
| 4080        | Longdean School                            | 240                         | 229     | 240     | 240     |          |         |         |         |         |         |         |         |         |         |
| 4096        | Kings Langley School                       | 190                         | 186     | 185     | 185     |          |         |         |         |         |         |         |         |         |         |
| 4499        | The Astley Cooper School                   | 180                         | 132     | 130     | 174     |          |         |         |         |         |         |         |         |         |         |
| 4619        | John F Kennedy Catholic School             | 180                         | 180     | 180     | 180     |          |         |         |         |         |         |         |         |         |         |
|             | Total Year 7 Pupil Demand                  |                             | 1119    | 1183    | 1248    | 1266     | 1334    | 1386    | 1389    | 1324    | 1428    | 1455    | 1488    | 1551    | 1537    |
|             | Total Year 7 Places Available              | 1,367                       |         |         |         | 1,367    | 1,363   | 1,363   | 1,363   | 1,363   | 1,363   | 1,363   | 1,363   | 1,363   | 1,363   |
|             | Surplus or Shortage of Year 7 Places (No.) |                             |         |         |         | 101      | 29      | -23     | -26     | 39      | -65     | -92     | -125    | -188    | -174    |
|             | Surplus or Shortage of Year 7 Places (%)   |                             |         |         |         | 7.4%     | 2.1%    | -1.7%   | -1.9%   | 2.9%    | -4.8%   | -6.7%   | -9.2%   | -13.8%  | -12.8%  |
|             | Surplus or Shortage of Year 7 Places (FE)  |                             |         |         |         | 3.4      | 1.0     | -0.8    | -0.9    | 1.3     | -2.2    | -3.1    | -4.2    | -6.3    | -5.8    |

## Watford

| 21.0 Watford                               |                                      |                             |         |         |         |          |         |         |         |         |         |         |         |         |         |
|--|--------------------------------------|-----------------------------|---------|---------|---------|----------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| School Code                                | School Name                          | Places Available<br>2020-21 | Actuals |         |         | Forecast |         |         |         |         |         |         |         |         |         |
|  |                                      |                             | 2017-18 | 2018-19 | 2019-20 | 2020-21  | 2021-22 | 2022-23 | 2023-24 | 2024-25 | 2025-26 | 2026-27 | 2027-28 | 2028-29 | 2029-30 |
| 4111                                       | Westfield Academy                    | 240                         | 167     | 178     | 230     |          |         |         |         |         |         |         |         |         |         |
| 5401                                       | Watford Grammar School for Boys      | 224                         | 197     | 225     | 224     |          |         |         |         |         |         |         |         |         |         |
| 5403                                       | Watford Grammar School for Girls     | 210                         | 182     | 210     | 210     |          |         |         |         |         |         |         |         |         |         |
| 5404                                       | Parmiter's School                    | 208                         | 208     | 211     | 209     |          |         |         |         |         |         |         |         |         |         |
| 5417                                       | Saint Michael's Catholic High School | 180                         | 182     | 181     | 182     |          |         |         |         |         |         |         |         |         |         |
| 6905                                       | Francis Combe Academy                | 210                         | 206     | 222     | 231     |          |         |         |         |         |         |         |         |         |         |
| Total Year 7 Pupil Demand                  |                                      |                             | 1142    | 1227    | 1286    | 1278     | 1325    | 1385    | 1375    | 1319    | 1341    | 1364    | 1397    | 1345    | 1333    |
| Total Year 7 Places Available              |                                      | 1,272                       |         |         |         | 1,272    | 1,272   | 1,272   | 1,272   | 1,272   | 1,272   | 1,272   | 1,272   | 1,272   | 1,272   |
| Surplus or Shortage of Year 7 Places (No.) |                                      |                             |         |         |         | -6       | -53     | -113    | -103    | -47     | -69     | -92     | -125    | -73     | -61     |
| Surplus or Shortage of Year 7 Places (%)   |                                      |                             |         |         |         | -0.5%    | -4.2%   | -8.9%   | -8.1%   | -3.7%   | -5.4%   | -7.2%   | -9.8%   | -5.7%   | -4.8%   |
| Surplus or Shortage of Year 7 Places (FE)  |                                      |                             |         |         |         | -0.2     | -1.8    | -3.8    | -3.4    | -1.6    | -2.3    | -3.1    | -4.2    | -2.4    | -2.0    |

## Bushey and Radlett

| 22.0 Bushey & Radlett                      |                      |                             |         |         |         |          |         |         |         |         |         |         |         |         |         |
|--|----------------------|-----------------------------|---------|---------|---------|----------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| School Code                                | School Name          | Places Available<br>2020-21 | Actuals |         |         | Forecast |         |         |         |         |         |         |         |         |         |
|  |                      |                             | 2017-18 | 2018-19 | 2019-20 | 2020-21  | 2021-22 | 2022-23 | 2023-24 | 2024-25 | 2025-26 | 2026-27 | 2027-28 | 2028-29 | 2029-30 |
| [6906]                                     | [The Bushey Academy] | 0                           | 214     | 216     | 0       |          |         |         |         |         |         |         |         |         |         |
| 4036                                       | Bushey Academy       | 210                         | 0       | 0       | 189     |          |         |         |         |         |         |         |         |         |         |
| 5408                                       | Bushey Meads School  | 200                         | 198     | 202     | 195     |          |         |         |         |         |         |         |         |         |         |
| 5410                                       | Queens' School       | 270                         | 264     | 270     | 270     |          |         |         |         |         |         |         |         |         |         |
| Total Year 7 Pupil Demand                  |                      |                             | 676     | 688     | 654     | 664      | 682     | 723     | 699     | 682     | 703     | 707     | 745     | 725     | 709     |
| Total Year 7 Places Available              |                      | 680                         |         |         |         | 680      | 680     | 680     | 680     | 680     | 680     | 680     | 680     | 680     | 680     |
| Surplus or Shortage of Year 7 Places (No.) |                      |                             |         |         |         | 16       | -2      | -43     | -19     | -2      | -23     | -27     | -65     | -45     | -29     |
| Surplus or Shortage of Year 7 Places (%)   |                      |                             |         |         |         | 2.4%     | -0.3%   | -6.3%   | -2.8%   | -0.3%   | -3.4%   | -4.0%   | -9.6%   | -6.6%   | -4.3%   |
| Surplus or Shortage of Year 7 Places (FE)  |                      |                             |         |         |         | 0.5      | -0.1    | -1.4    | -0.6    | -0.1    | -0.8    | -0.9    | -2.2    | -1.5    | -1.0    |

## Rickmansworth

| 20.0        | Rickmansworth                                     |                             |            |            |            |             |              |              |              |              |             |              |              |             |             |
|-------------|---|-----------------------------|------------|------------|------------|-------------|--------------|--------------|--------------|--------------|-------------|--------------|--------------|-------------|-------------|
| School Code | School Name                                       | Places Available<br>2020-21 | Actuals    |            |            | Forecast    |              |              |              |              |             |              |              |             |             |
|             |   |                             | 2017-18    | 2018-19    | 2019-20    | 2020-21     | 2021-22      | 2022-23      | 2023-24      | 2024-25      | 2025-26     | 2026-27      | 2027-28      | 2028-29     | 2029-30     |
| 4007        | The Reach Free School                             | 120                         | 113        | 120        | 118        |             |              |              |              |              |             |              |              |             |             |
| 4025        | Croxley Danes School                              | 180                         | 120        | 179        | 178        |             |              |              |              |              |             |              |              |             |             |
| 5400        | Rickmansworth School                              | 226                         | 196        | 228        | 225        |             |              |              |              |              |             |              |              |             |             |
| 5418        | Saint Joan of Arc Catholic School                 | 210                         | 212        | 223        | 223        |             |              |              |              |              |             |              |              |             |             |
| 5421        | St Clement Danes School                           | 240                         | 240        | 240        | 238        |             |              |              |              |              |             |              |              |             |             |
|             | <b>Total Year 7 Pupil Demand</b>                  |                             | <b>881</b> | <b>990</b> | <b>982</b> | <b>969</b>  | <b>981</b>   | <b>1025</b>  | <b>1012</b>  | <b>1006</b>  | <b>952</b>  | <b>991</b>   | <b>979</b>   | <b>973</b>  | <b>919</b>  |
|             | <b>Total Year 7 Places Available</b>              | <b>976</b>                  |            |            |            | <b>976</b>  | <b>976</b>   | <b>976</b>   | <b>976</b>   | <b>976</b>   | <b>976</b>  | <b>976</b>   | <b>976</b>   | <b>976</b>  | <b>976</b>  |
|             | <b>Surplus or Shortage of Year 7 Places (No.)</b> |                             |            |            |            | <b>7</b>    | <b>-5</b>    | <b>-49</b>   | <b>-36</b>   | <b>-30</b>   | <b>24</b>   | <b>-15</b>   | <b>-3</b>    | <b>3</b>    | <b>57</b>   |
|             | <b>Surplus or Shortage of Year 7 Places (%)</b>   |                             |            |            |            | <b>0.7%</b> | <b>-0.5%</b> | <b>-5.0%</b> | <b>-3.7%</b> | <b>-3.1%</b> | <b>2.5%</b> | <b>-1.5%</b> | <b>-0.3%</b> | <b>0.3%</b> | <b>5.8%</b> |
|             | <b>Surplus or Shortage of Year 7 Places (FE)</b>  |                             |            |            |            | <b>0.2</b>  | <b>-0.2</b>  | <b>-1.6</b>  | <b>-1.2</b>  | <b>-1.0</b>  | <b>0.8</b>  | <b>-0.5</b>  | <b>-0.1</b>  | <b>0.1</b>  | <b>1.9</b>  |

Rickmansworth is included for information. Following the opening of two new schools in this area, The Reach Free School and Croxley Danes School, there is a closer match between supply and demand.

## Borehamwood

| 16.0        | Borehamwood                                       |                             |            |            |            |             |             |             |              |             |              |              |               |              |              |
|-------------|---|-----------------------------|------------|------------|------------|-------------|-------------|-------------|--------------|-------------|--------------|--------------|---------------|--------------|--------------|
| School Code | School Name                                       | Places Available<br>2020-21 | Actuals    |            |            | Forecast    |             |             |              |             |              |              |               |              |              |
|             |   |                             | 2017-18    | 2018-19    | 2019-20    | 2020-21     | 2021-22     | 2022-23     | 2023-24      | 2024-25     | 2025-26      | 2026-27      | 2027-28       | 2028-29      | 2029-30      |
| 4001        | Hertswood Academy                                 | 270                         | 242        | 234        | 222        |             |             |             |              |             |              |              |               |              |              |
| 4802        | Yavneh College                                    | 150                         | 150        | 151        | 180        |             |             |             |              |             |              |              |               |              |              |
|             | <b>Total Year 7 Pupil Demand</b>                  |                             | <b>392</b> | <b>385</b> | <b>402</b> | <b>394</b>  | <b>396</b>  | <b>414</b>  | <b>423</b>   | <b>413</b>  | <b>437</b>   | <b>440</b>   | <b>465</b>    | <b>451</b>   | <b>454</b>   |
|             | <b>Total Year 7 Places Available</b>              | <b>420</b>                  |            |            |            | <b>420</b>  | <b>420</b>  | <b>420</b>  | <b>420</b>   | <b>420</b>  | <b>420</b>   | <b>420</b>   | <b>420</b>    | <b>420</b>   | <b>420</b>   |
|             | <b>Surplus or Shortage of Year 7 Places (No.)</b> |                             |            |            |            | <b>26</b>   | <b>24</b>   | <b>6</b>    | <b>-3</b>    | <b>7</b>    | <b>-17</b>   | <b>-20</b>   | <b>-45</b>    | <b>-31</b>   | <b>-34</b>   |
|             | <b>Surplus or Shortage of Year 7 Places (%)</b>   |                             |            |            |            | <b>6.2%</b> | <b>5.7%</b> | <b>1.4%</b> | <b>-0.7%</b> | <b>1.7%</b> | <b>-4.0%</b> | <b>-4.8%</b> | <b>-10.7%</b> | <b>-7.4%</b> | <b>-8.1%</b> |
|             | <b>Surplus or Shortage of Year 7 Places (FE)</b>  |                             |            |            |            | <b>0.9</b>  | <b>0.8</b>  | <b>0.2</b>  | <b>-0.1</b>  | <b>0.2</b>  | <b>-0.6</b>  | <b>-0.7</b>  | <b>-1.5</b>   | <b>-1.0</b>  | <b>-1.1</b>  |

## APPENDIX 2

## SOUTH -WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH: SHORTLISTED POTENTIAL SCHOOL SITE

### SITE DETAILS

|                                   |   |                    |  |
|-----------------------------------|---|--------------------|--|
| <b>Site Reference and address</b> | [insert Settlement name]: Site [insert site ref A-Z]<br>[Site address]<br>Site identification plan: [5309/]<br>Aerial photograph: [5309/]<br>Development principles plan: [5309/] |                    |  |
| <b>Site area</b>                  | [insert] ha<br>Building zone: [insert] ha<br>Playing Fields zone: [insert] ha   |                    |  |
| <b>Existing use/occupiers</b>     | [insert land use/ any occupation]   |                    |  |
| <b>Land ownership</b>             | [insert Land Registry details – all owners]<br>[insert any known information about site ownership/availability]   |                    |  |
| <b>Site availability</b>          | [insert any known information about site availability]  |                    |  |
| <b>Brownfield Land Register</b>   | [insert Y/N]  |                    |  |
| <b>Planning history</b>           | [insert any previous planning applications on the site]   |                    |  |
| <b>Buildings</b>                  | [insert all buildings on the site, including number of storeys]   |                    |  |
| <b>Adjoining uses</b>             | North:  | [insert land uses] |  |
|                                   | East:   | [insert land uses] |  |
|                                   | South:  | [insert land uses] |  |
|                                   | West:   | [insert land uses] |  |
| <b>Topography</b>                 | [insert description of any changes in levels, falls and direction of]   |                    |  |
| <b>Water courses</b>              | [Insert description] from aerial photographs, OS maps or public vantage points.   |                    |  |
| <b>Vegetation</b>                 | [insert description of principal tree groups, locations of tree groups, hedgerows]  |                    |  |

### ACCESSIBILITY

|                         |  |
|-------------------------|--|
| <b>Vehicular access</b> | [Insert description of any existing access points major or minor and the road they take access/egress from] Comment on road type ie A road /B road / unclassified road / narrow country lane / suburban residential road etc?) |
|-------------------------|--|

|                                       |   |
|---------------------------------------|---|
| <b>Cycle access</b>                   | [Insert description of any existing cycle routes along the site boundaries / adjoining site]  |
| <b>Pedestrian access</b>              | [Insert description of any existing footways routes along the site boundaries / adjoining site]   |
| <b>Public transport</b>               | [insert description of bus stop locations, distance from site and bus routes]   |
| <b>High level transport appraisal</b> | A high level transport appraisal prepared by Stomor Civil Engineering Consultants concludes that [insert conclusions from high level transport appraisal] |

## ENVIRONMENTAL IMPACT

|   |   |
|---|---|
| <b>Landscape and visual impact</b>        | <p>[insert a description of whether the site is:</p> <ul style="list-style-type: none"> <li>- Exposed to long distance views to the [insert compass directions]</li> <li>- Partially exposed to long distance views to the [insert compass directions]</li> <li>- Enclosed from long distance views to the [insert compass directions]</li> </ul> <p>[insert a description of any landscape character designations]</p> |
| <b>Impact on residential amenities:</b>   | [insert any adjacent or nearby residential areas that may be affected by a school, noise, loss of privacy, overbearing mass]  |
| <b>Ecology:</b>                           | [Insert a description of any vegetation or land uses that may be of ecological interest e.g. hedges, trees, grassland, ponds] [Insert any known ancient woodland/veteran trees]   |
| <b>Noise sources</b>                      | [Insert any nearby roads, railways, airfields or other noise generating sources]  |
| <b>Flood risk</b>                         | [Insert flood zone]   |
| <b>Surface water flooding</b>             | [Insert surface water flooding information if available]  |
| <b>Groundwater source protection area</b> | [Confirm whether the site is in a groundwater source protection zone]   |
| <b>Air quality</b>                        | [Confirm whether the site is in an Air Quality Management Area or close to source of poor air quality such as major road]   |
| <b>Minerals</b>                           | [Confirm whether the site lies in a Minerals Consultation Area - Sand and Gravel Belt]  |
| <b>Agricultural land quality</b>          | [Insert Agricultural land grade if relevant if not then N/A]  |
| <b>Rights of way</b>                      | [insert any public rights of way that run through the site, adjoin the site and their type e.g. footpath, bridleway]  |

## EXISTING PLANNING AND DESIGNATION CONSTRAINTS

|   |  |
|---|--|
| <b>Existing and emerging local plan site specific</b> | [Insert planning designations from adopted local plan proposals map and any plan nearing adoption and insert any SHELLA designation] |
|---|--|

|  |   |
|--|---|
| <b>designations</b>  |   |
| <b>Heritage assets: archaeology</b>  | [Insert any archaeological designations on the adopted Local Plan Proposals Map]  |
| <b>Designated heritage assets</b>  | [Insert a description of any world heritage site, Scheduled monument, listed buildings, Conservation areas, Registered Park or Garden, Registered battlefield, either on the site itself or adjacent to the site] and note boundary adjacency                       |
| <b>Designated rural areas</b>  | [insert a description of National Park, Areas of Outstanding Natural Beauty]  |
| <b>International, National and locally designated sites of importance for biodiversity and habitat sites</b> | [insert a description of Special Areas of Conservation, Sites of Community Importance, Special Protection Areas, RAMSAR sites, national sites (Sites of Special Scientific Interest) and locally designated sites including wildlife sites) and wildlife corridors] |

## SITE EVALUATION

### Positive site attributes [delete as necessary from this section]:

1. The site is of optimal / sufficient size for 6fe/8fe/10fe.
2. The site is in single ownership.
3. The site is available.
4. The site is [flat/gentle level changes] and re-grading would be minimal/limited.
5. Vehicular access [could be achieved from – insert adjoining road] with suitable mitigation/improvements.
6. Pedestrian/cycle access [could be achieved from – insert adjoining road] with suitable mitigation/improvements.
7. The site lies adjacent/within xm walking distance of bus stops and bus routes.
8. Site development would not be exposed to long distance views in the wider landscape.
9. The site has [no significant/relatively small] areas of vegetation that would require removal to accommodate a secondary school.
10. The site lies adjacent to the urban area of [insert settlement].
11. There would be no impacts on preserved trees.
12. There would be minor ecological impact [subject to further investigations].
13. The site is not at risk of flooding [subject to further investigations].
14. The site is not located near any noise sources.
15. The site lies outside the Green Belt.
16. The site lies outside an AQMA.
17. The site does not lie in a Minerals Consultation Area.
18. The site is not in an Area of Archaeological Importance.
19. There would be no impacts on designated heritage assets.
20. The site is not in a designated rural area.
21. The site does not have any international, national or local wildlife, habitat or biodiversity designations.

22. The site does not have any local plan allocation.
23. The site is not an identified HELAA site.
24. The site has low grade agricultural land classification [if relevant].
25. The site is not traversed by rights of way.
26. The site has a single landowner/is in the ownership of HCC.

**Negative site attributes [delete as necessary from this section]:**

1. The site is not of optimal / sufficient size for 6fe/8fe/10fe.
2. The site is in more than one ownership.
3. The site is not known to be available.
4. The site is [sloping/significant level changes] and re-grading would be [required/significant].
5. Vehicular access [could not be achieved from – insert adjoining road] with suitable mitigation/improvements.
6. Pedestrian/cycle access [could not be achieved from – insert adjoining road] with suitable mitigation/improvements.
7. The site does not lie within [x km] walking distance of bus stops and bus routes.
8. Site development would be exposed to long distance views in the wider landscape.
9. The site has [significant/relatively large] areas of vegetation that would require removal to accommodate a secondary school.
10. The site does not lie adjacent to the urban area of [insert settlement].
11. There would be impacts on preserved trees.
12. There would be more than minor ecological impact [subject to further investigations].
13. The site is at risk of flooding [subject to further investigations].
14. The site is located near noise sources.
15. The site lies in the Green Belt.
16. The site lies in an AQMA.
17. The site lies in a Minerals Consultation Area.
18. The site is in an Area of Archaeological Importance.
19. There would be impacts on designated heritage assets.
20. The site is in a designated rural area.
21. The site has an international, national or local wildlife, habitat or biodiversity designations [insert].
22. The site has a local plan allocation.
23. The site does have an HELAA allocation [insert description].
24. The site has high grade agricultural land classification [if relevant].
25. The site is traversed by rights of way.
26. The site more than one landowner/is not in the ownership of HCC.



## SITE LAYOUT PRINCIPLES

A BB103 compliant 6fe/8fe/10fe secondary school site [could/could not] be accommodated on this site:

1. Development principles plan 5309/
2. Total site area: [ha]
3. Build zone: [ha]
4. Building footprint: [sqm]
5. Vehicular access/egress: [road]
6. Pedestrian access: [road]

## CONCLUSION


This site is/is not recommended for comparative assessment with other sites.

Further site investigations are recommended comprising:

[insert list of technical /environmental investigations]

## APPENDIX 3





|  |         |
|--|---------|
| <b>BORE 00</b> BOREHAMWOOD OPTION SITES                |         |
| 01 LAND WEST OF A1(M)                                  | 11.34ha |
| 02 LAND NORTH OF ROWLEY LANE                           | 11.64ha |
| 03 LAND EAST OF GREEN STREET (PARCEL A)                | 11.22ha |
| 04 LAND EAST OF GREEN STREET (PARCEL B)                | 10.71ha |
| 05 LAND EAST OF GREEN STREET (PARCEL C)                | 10.98ha |
| 06 LAND NORTH OF ALLUM LANE                            | 10.97ha |
| 07 LAND SOUTH OF ALLUM LANE                            | 16.00ha |
| 08 LAND SOUTH OF BARNET LANE                           | 11.18ha |
| <b>HCC.1-14</b> HERTFORDSHIRE COUNTY COUNCIL OWNERSHIP |         |
| HCC.1 THE LEAD   | 0.40ha  |
| HCC.2 DAY CENTRE                                       | 3.13ha  |
| HCC.3 MERYFIELD COMMUNITY SCHOOL                       | 3.77ha  |
| HCC.4 COWLEY HILL & WOODLANDS PRIMARY SCHOOLS          | 3.13ha  |
| HCC.5 ST TERESA'S RC SCHOOL PLAYING FIELDS             | 0.74ha  |
| HCC.6 CHEEKY MONKEYS DAY NURSERY                       | 0.40ha  |
| HCC.7 BOREHAMWOOD FIRE STATION                         | 0.37ha  |
| HCC.8 MAXWELL PARK COMMUNITY CENTRE                    | 0.16ha  |
| HCC.9 MARTINS WALK PLAYSPACE                           | 1.06ha  |
| HCC.10 STARJUMPS NURSERY                               | 0.60ha  |
| HCC.11 SUMMERSWOOD PRIMARY SCHOOL                      | 1.90ha  |
| HCC.12 YAVNEH COLLEGE/MONKSMEAD SCHOOL PLAYING FIELDS  | 5.65ha  |
| HCC.13 KENILWORTH SCHOOL                               | 1.90ha  |
| HCC.14 SAFFRON GREEN PRIMARY SCHOOL                    | 1.58ha  |
| <b>PF.1-11</b> PLAYING FIELDS/PLAY SPACE               |         |
| PF.1 WALSHFORD WAY                                     | 0.29ha  |
| PF.2 BELFORD ROAD                                      | 2.30ha  |
| PF.3 AYCLIFFE PARK                                     | 5.41ha  |
| PF.4 ABERFORD PARK                                     | 6.51ha  |
| PF.5 OLD HABERDASHERS SPORTS GROUND                    | 4.00ha  |
| PF.6 MEADOW PARK                                       | 8.78ha  |
| PF.7 MAXWELL PARK                                      | 3.56ha  |
| PF.8 KENILWORTH PARK                                   | 2.67ha  |
| PF.9 WANSFORD PARK                                     | 3.91ha  |
| PF.10 RIFON PARK                                       | 4.10ha  |
| PF.11 STARJUMPS NURSERY                                | 0.20ha  |
| PF.12 FARRIERS WAY                                     | 0.66ha  |
| <b>OL.1-11</b> OPEN LAND                               |         |
| OL.1 WALSHFORD WAY                                     | 0.84ha  |
| OL.2 THIRSKCLIFFE NATURE PARK                          | 2.87ha  |
| OL.3 HAGGERSTON ROAD                                   | 1.06ha  |
| OL.4 ORGAN HALL ROAD                                   | 3.07ha  |
| OL.5 ABERFORD PARK                                     | 1.40ha  |
| OL.6 GATESHEAD ROAD                                    | 0.12ha  |
| OL.7 CROWN ROAD  | 0.39ha  |
| OL.8 GROVE ROAD  | 1.07ha  |
| OL.9 DENHAM WAY  | 4.73ha  |
| OL.10 BANKS ROAD                                       | 0.81ha  |
| OL.11 LEMS福德 COURT                                     | 0.16ha  |
| <b>AL.1</b> ALLOTMENTS                                 |         |
| AL.1 FURZEHILL ROAD ALLOTMENTS                         | 2.01ha  |
| <b>E.1-3</b> EMPLOYMENT AREAS                          |         |
| E.1 TELEVISION STUDIOS                                 | 6.29ha  |
| E.2 ELSTREE WAY  | 37.49ha |
| E.3 STERLING WAY                                       | 7.00ha  |
| <b>OTHER PRIMARY AND SECONDARY SCHOOLS</b>             |         |
| <b>GREEN BELT BOUNDARY</b>                             |         |
| <b>HOUSING SITES UNDER CONSIDERATION</b>               |         |
| <b>EMPLOYMENT SITES UNDER CONSIDERATION</b>            |         |
| <b>POLICY SADM9 - SAFEGUARDED LAND FOR EMPLOYMENT</b>  |         |
| <b>HERTFORDSHIRE LOCAL PLAN 2012-2027</b>              |         |
| <b>POLICY MAP NOVEMBER 2016</b>                        |         |

REVISION A:  
Amendments to potential sites following client discussions  
HNA/28-05-2020

REVISION B:  
Amendments following further information received from HBC  
(09-07-2020)  
HNA/10-07-2020

REVISION C:  
Study area amended, BORE08 site added  
HNA/29-07-2020


## SOUTH WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH

Borehamwood: Urban area

|            |            |         |
|------------|------------|---------|
| PROJECT NO | DRAWING NO | REV     |
| 5309       | 300        | C       |
| DRAWN      | DATE       | SCALE   |
| HNA        | JUNE 2020  | 1:10000 |







- BORE 00** BOREHAMWOOD OPTION SITES
- 01 LAND WEST OF A1(M) 11.34ha
  - 02 LAND NORTH OF ROWLEY LANE 11.64ha
  - 03 LAND EAST OF GREEN STREET (PARCEL A) 11.22ha
  - 04 LAND EAST OF GREEN STREET (PARCEL B) 10.71ha
  - 05 LAND EAST OF GREEN STREET (PARCEL C) 10.98ha
  - 06 LAND NORTH OF ALLUM LANE 10.97ha
  - 07 LAND SOUTH OF ALLUM LANE 16.00ha
  - 08 LAND SOUTH OF BARNET LANE 11.18ha
- HERTFORDSHIRE COUNTY COUNCIL OWNERSHIP**
- STUDY AREA**
- LOCAL AUTHORITY BOUNDARY**
- GREEN BELT BOUNDARY**
- WOODLAND AREAS**
- CONSERVATION AREA**
- PARK/GARDEN**
- GREEN CHAIN (LONDON BOROUGH OF BARNET)**
- SCHEDULED ANCIENT MONUMENT**
- AREA OF ARCHAEOLOGICAL INTEREST**
- GOLF COURSE**
- PLAYING FIELDS**
- LANDSCAPE DESIGNATIONS**
- LCA: LANDSCAPE CONSERVATION AREA
  - LDA: LANDSCAPE DEVELOPMENT AREA
  - CLA: CHILTERN'S LANDSCAPE AREA
  - CRVLA: CHILTERN RIVER VALLEYS LANDSCAPE AREA
- SSSI/NATURE RESERVE**
- SITE OF METROPOLITAN IMPORTANCE FOR NATURE CONSERVATION (LONDON BOROUGH OF BARNET)**
- WILDLIFE SITES**
- REGIONALLY IMPORTANT GEOLOGICAL SITE SITES**
- NOISE SOURCE**
- ENVIRONMENT AGENCY FLOOD ZONE 2**
- ENVIRONMENT AGENCY FLOOD ZONE 3**
- ENVIRONMENT AGENCY FLOOD STORAGE AREA**
- PUBLIC FOOTPATHS**
- RESTRICTED BYWAY**
- BYWAY**
- BRIDLEWAY**
- OTHER PRIMARY AND SECONDARY SCHOOLS**
- HOUSING SITES UNDER CONSIDERATION**
- EMPLOYMENT SITES UNDER CONSIDERATION**

REVISION A:  
Amendments to potential sites following client discussions  
HNA/28-05-2020

REVISION B:  
Amendments following further information received from HBC  
(09-07-2020)  
HNA/10-07-2020

REVISION C:  
Study area amended, BORE08 site added  
HNA/29-07-2020

### SOUTH WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH

Borehamwood: Non urban area

| PROJECT NO | DRAWING NO | REV     |
|------------|------------|---------|
| 5309       | 301        | C       |
| DRAWN      | DATE       | SCALE   |
| HNA        | JUNE 2020  | 1:10000 |



## APPENDIX 4

## SOUTH -WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH: SHORTLISTED POTENTIAL SCHOOL SITE

### SITE DETAILS

|                                   |   |   |
|-----------------------------------|---|---|
| <b>Site Reference and address</b> | Borehamwood Site: BORE01<br>Land west of A1(M), Borehamwood<br>Site identification plan: [5309/310]<br>Aerial photograph: [5309/311]  |   |
| <b>Site area</b>                  | 11.12 ha  |   |
| <b>Existing use/occupiers</b>     | The site was historically used as a private sports ground for cricket and tennis and is currently partly in use as a car/lorry park   |   |
| <b>Land ownership</b>             | LEGAL AND GENERAL ASSURANCE SOCIETY LIMITED (Co. Regn. No. 166055) of Temple Court, 11 Queen Victoria Street, London EC4N 4JP.  |   |
| <b>Site availability</b>          | Unlikely to be available. Planning application has been granted permission for the development of Sky Studios Elstree, a state-of-the-art TV and film studio. The development is expected to be open in 2022.   |   |
| <b>Brownfield Land Register</b>   | No.   |   |
| <b>Planning history</b>           | An outline planning application for a Centre for Sporting Excellence was submitted in October 2014 (ref. 14/1735/OUT). The scheme was not implemented and has subsequently expired.<br><br>20/0315/FULEI   Development of film/production studios (Use Class B1b) and ancillary floorspace, new access arrangements, car parking, landscaping, infrastructure and associated works.   Land East Of Rowley Lane Borehamwood Hertfordshire – Granted. |   |
| <b>Buildings</b>                  | There are existing single storey containers and structures scattered throughout the site.   |   |
| <b>Adjoining uses</b>             | North:  | To the north of the site are agricultural fields.   |
|                                   | East:   | The site is bounded to the east by the A1(M), beyond which is agricultural land and a golf course.  |
|                                   | South:  | An area of woodland abuts the site to the south, beyond this is a large Holiday Inn hotel.  |
|                                   | West:   | The site is bounded to the west by Rowley Lane. There are buildings of various uses fronting onto Rowley Lane including residential flats, office space and a BP petrol station and convenience shop. |
| <b>Topography</b>                 | The site is almost entirely level.  |   |
| <b>Water courses</b>              | The Mimmshall Brook runs through the site.  |   |

|   |  |
|---|--|
| <b>Vegetation</b>                         | There is a mature hedgerow/tree belt between the site and Rowley Lane and the A1(M). Within the site vegetation is predominantly limited to the eastern half of the site where there are further hedgerows.  |
| <b>ACCESSIBILITY</b>                      |  |
| <b>Vehicular access</b>                   | Rowley Lane (Principal A road) runs along the site to the west and connects to the A1 via Elstree Road further to the south. Vehicular access to the site is via Rowley Lane.  |
| <b>Cycle access</b>                       | Rowley Lane and Elstree Way have dedicated cycle lanes.  |
| <b>Pedestrian access</b>                  | There is a pedestrian footpath opposite the site on the western side of Rowley Lane.   |
| <b>Public transport</b>                   | <p>The closest rail station to the site is Elstree and Borehamwood Station, situated to the west of the site. This station lies approximately 2.4km (30min walking distance or 9min cycle distance) from the centre of the site.</p> <p>A total of five bus stops are situated in close proximity to the application site. The closest bus stop to the site (Borehamwood, Rowley Lane, southbound) lies approximately 0.16km (3min walking distance) to the south of the site. This stop is served by bus routes 398 (Potters Bar – Borehamwood). Bus route 107 (Edgware – New Barnet) can be accessed via bus stops on Elstree Way.</p> |
| <b>High level transport appraisal</b>     | A high-level transport appraisal is not recommended.   |
| <b>ENVIRONMENTAL IMPACT</b>               |  |
| <b>Landscape and visual impact</b>        | The site is well screened from all directions due to intervening vegetation and the level nature of the land. There will be private views of the site from the west due to the high scale of the adjacent buildings.   |
| <b>Impact on residential amenities:</b>   | None likely.   |
| <b>Ecology:</b>                           | Ecological value is likely limited to the watercourse within the site and the hedgerows and trees. AN ecological appraisal submitted with the pending planning application found that bats are utilising the mature trees and the existing buildings on site.  |
| <b>Noise sources</b>                      | Rowley Lane and the A1(M) are both adjacent to the site and represent significant noise sources. There is also a depot to the west of the site.  |
| <b>Flood risk</b>                         | Much of the site is within Flood Zone 1. However, areas to the south and west of the site are within Flood Zone 3, reflecting the route of the Mimmshall Brook.  |
| <b>Surface water flooding</b>             | Most of the site is at very low risk. However, there are areas of low-high risk across the site, predominantly to the south and west.  |
| <b>Groundwater source protection area</b> | None.  |

|                                  |  |
|----------------------------------|--|
| <b>Air quality</b>               | Adjacent to Rowley Lane, A1(M) and petrol station.   |
| <b>Minerals</b>                  | Sand and Gravel Belt   |
| <b>Agricultural land quality</b> | 3a/3b  |
| <b>Rights of way</b>             | There are no public rights of way through the site. Elstree and Borehamwood Footpath 019 is just west of the site. |

### EXISTING PLANNING AND DESIGNATION CONSTRAINTS

|  |  |
|--|--|
| <b>Existing and emerging local plan site specific designations</b>   | To the north of the site is Green Belt land, however the site itself has been removed from the Green Belt and is now identified as 'Safeguarded Land for Employment Development' under Policy SADM9<br><br>Identified as site HEL206 in HELAA 2019 Report. (Not formal allocation) |
| <b>Heritage assets: archaeology</b>  | None.  |
| <b>Designated heritage assets</b>  | None.  |
| <b>Designated rural areas</b>  | None.  |
| <b>International, National and locally designated sites of importance for biodiversity and habitat sites</b> | None.  |

### SITE EVALUATION

#### Positive site attributes:

1. The site is of optimal / sufficient size for 8fe
2. The site is in single ownership.
3. The site is flat and re-grading would be minimal.
4. Vehicular access could be achieved from Rowley Lane with suitable mitigation/improvements.
5. Pedestrian/cycle access Rowley Lane with suitable mitigation/improvements.
6. The site lies adjacent/within 400m walking distance of bus stops and bus routes.
7. Site development would not be exposed to long distance views in the wider landscape.
8. The site has relatively small areas of vegetation that would require removal to accommodate a secondary school.
9. The site lies adjacent to the urban area of Borehamwood
10. There would be no impacts on preserved trees.
11. There would be minor ecological impact [subject to further investigations].
12. The site lies outside the Green Belt.
13. The site lies outside an AQMA.
14. The site is not in an Area of Archaeological Importance.



15. There would be no impacts on designated heritage assets.
16. The site is not in a designated rural area.
17. The site does not have any international, national or local wildlife, habitat or biodiversity designations.
18. The site does not have any local plan allocation.
19. The site is not traversed by rights of way.
20. The site has a single landowner/is in the ownership of HCC.

**Negative site attributes:**

1. The site is unlikely to be available due to ongoing planning application
2. The site is at risk of flooding [subject to further investigations].
3. The site is located near noise sources.
4. The site lies in a Minerals Consultation Area.
5. The site does have an HELAA allocation [HEL206].
6. The site has moderate-good grade agricultural land classification [if relevant].

**SITE LAYOUT PRINCIPLES**

A BB103 compliant 8fe secondary school site could not be accommodated on this site.

**CONCLUSION**

The site is located on land west of the A1(m) and east of Rowley Lane (plan 5309/301/C). The existing use is a car/lorry park. The site is in single ownership and almost entirely level. The site is an optimal size for an 8fe school. Upon further investigation the site is unlikely to be available. Planning permission has been granted for the development of Sky Studios Elstree, a TV and film studio expected to be open in 2022. This site was not recommended for high level transport appraisal or for comparative assessment with other sites.









**BORE 01**

**SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH**

Aerial photograph: BORE01

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 311        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | JUNE 2020  | 1:2500 @A2 |





## SOUTH -WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH: SHORTLISTED POTENTIAL SCHOOL SITE

### SITE DETAILS

|                                   |  |  |
|-----------------------------------|--|--|
| <b>Site Reference and address</b> | Borehamwood Site: BORE02<br>Land north of Rowley Lane, Borehamwood<br>Site identification plan: 5309/320<br>Aerial photograph: 5309/321<br>Development principles plan: 5309/322 |  |
| <b>Site area</b>                  | 11.74 ha   |  |
| <b>Existing use/occupiers</b>     | Agricultural pasture land  |  |
| <b>Land ownership</b>             | WROTHAM PARK SETTLED ESTATES of Estate Office, Wrotham Park, Barnet EN5 4SB.   |  |
| <b>Site availability</b>          | Site in HELAA 2019 report.   |  |
| <b>Brownfield Land Register</b>   | No   |  |
| <b>Planning history</b>           | None.  |  |
| <b>Buildings</b>                  | None.  |  |
| <b>Adjoining uses</b>             | North:   | To the north is agricultural land.   |
|                                   | East:  | To the east is agricultural land.  |
|                                   | South:   | The site is bounded to the south by Rowley Lane. Fronting Rowley Lane are farm buildings and The Mops and Broops Public House. |
|                                   | West:  | The site is bounded to the west by Well End Road. There is a row of dwellings fronting onto the road.                          |
| <b>Topography</b>                 | The site is predominantly level with a very gentle incline from east to west.  |  |
| <b>Water courses</b>              | None.  |  |
| <b>Vegetation</b>                 | The site is bounded entirely by hedgerow scattered with mature trees. There are hedgerows within the site defining the field boundaries.   |  |

### ACCESSIBILITY

|                         |  |
|-------------------------|--|
| <b>Vehicular access</b> | Well End Road is situated to the west of the site and is an Unnumbered C Road with 30mph restriction. To the south is Rowley Lane, an unclassified U Road. Access may be possible from either road with adequate improvements. |
|-------------------------|--|

|                                       |  |
|---------------------------------------|--|
| <b>Cycle access</b>                   | None.  |
| <b>Pedestrian access</b>              | There is a pedestrian footpath on the western side of Well End Road.   |
| <b>Public transport</b>               | Alexandra Road bus stop is the nearest bus stop to the site, a 0.16km walk (2 minutes). This provides access to route B3 which connects to Borehamwood Town Centre.  |
| <b>High level transport appraisal</b> | <p>A high-level transport appraisal prepared by Stomor Civil Engineering Consultants concludes that there are some reservations on the suitability of increased vehicle movements along the rural section of Rowley Lane and the access onto the A1 from Holmshill Lane. A detailed review of the potential impact of school related traffic along these roads will need to be undertaken and significant improvements to the road layout will be required in order to provide a safe and suitable route, or alternatively, measures to discourage school related travel along this route.</p> <p>There are also potential capacity issues along Potters Lane for vehicles and cyclists, which is likely to be on a key desire line from the northern side of Borehamwood.</p> <p>If the concerns identified above can be mitigated to a suitable standard, then, in principle, the site may be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment.</p> <p>Footways along residential roads to the west and south-west of the site are generally considered suitable. However, new crossing facilities are likely to be required.</p> <p>Bus accessibility to the site from Borehamwood and Elstree is reasonable, with bus stops on Alexandra Road providing access to route B3. However, existing links to the wider area would be from stops available on the B5378 Shenley Road and the A5135 Elstree Way which are over 1km from the school site. Improved accessibility between the site and the local bus stops should be considered as part of proposals.</p> <p>Due to the Covid-19 pandemic, traffic conditions at the time of writing this High-Level Assessment do not reflect former 'typical' traffic conditions. However, a desktop review of available traffic information has been undertaken which indicates that the main local roads to the south of the site experience a level of congestion at peak times.</p> |

## ENVIRONMENTAL IMPACT

|   |   |
|---|---|
| <b>Landscape and visual impact</b>      | The site appears to be well enclosed by existing vegetation from all directions.  |
| <b>Impact on residential amenities:</b> | Limited impact.   |
| <b>Ecology:</b>                         | There are trees and hedgerows surrounding the perimeter of the site and dispersed throughout. These are likely to provide habitats for birds and invertebrates. |
| <b>Noise sources</b>                    | None significant.   |
| <b>Flood risk</b>                       | Flood Zone 1 – Very low risk  |

|   |   |
|---|---|
| <b>Surface water flooding</b>             | Very low risk   |
| <b>Groundwater source protection area</b> | None  |
| <b>Air quality</b>                        | None  |
| <b>Minerals</b>                           | Sand and Gravel Belt  |
| <b>Agricultural land quality</b>          | 3a/3b   |
| <b>Rights of way</b>                      | Shenley footpath 016 runs along the eastern boundary of the site. |

### EXISTING PLANNING AND DESIGNATION CONSTRAINTS

|  |   |
|--|---|
| <b>Existing and emerging local plan site specific designations</b>   | Green Belt<br>HELAA site – HEL376a  |
| <b>Heritage assets: archaeology</b>  | None.   |
| <b>Designated heritage assets</b>  | To the south of the site is a Grade II listed building known as Nelson Cottage and another Grade II listed barn at Rowley Farm. |
| <b>Designated rural areas</b>  | None.   |
| <b>International, National and locally designated sites of importance for biodiversity and habitat sites</b> | None.   |

### SITE EVALUATION

#### Positive site attributes:

1. The site is of optimal / sufficient size for 8f/e
2. The site is in single ownership.
3. The site is available.
4. The site has gentle level changes and re-grading would be minimal.
5. Vehicular access could likely be achieved from Well End Road with suitable mitigation/improvements.
6. Pedestrian/cycle access could likely be achieved from Well End Road with suitable mitigation/improvements.
7. The site lies adjacent/within 400m walking distance of bus stops and bus routes.
8. Site development would not be exposed to long distance views in the wider landscape.
9. The site has relatively small areas of vegetation that would require removal to accommodate a secondary school.
10. The site lies adjacent to the urban area of Borehamwood.
11. There would be no impacts on preserved trees.

12. There would be minor ecological impact [subject to further investigations].
13. The site is not at risk of flooding [subject to further investigations].
14. The site is not located near any noise sources.
15. The site lies outside an AQMA.
16. The site is not in an Area of Archaeological Importance.
17. The site is not in a designated rural area.
18. The site does not have any international, national or local wildlife, habitat or biodiversity designations.
19. The site does not have any local plan allocation.
20. The site is not traversed by rights of way.
21. The site has a single landowner.

#### **Negative site attributes:**

1. The site lies in a Minerals Consultation Area.
2. There would be impacts on designated heritage assets.
3. The site does have an HELAA allocation [HEL376a].
4. The site has moderate-good grade agricultural land classification [if relevant].
5. There are power lines running across the site which would require burying.

#### **SITE LAYOUT PRINCIPLES**

A BB103 compliant 8fe secondary school site could be accommodated on this site:

1. Development principles plan 5309/322
2. Total site area: [11.74ha]
3. Build zone: [3.56ha]
4. Playing Field zone: [8.18ha]
5. Building footprint: [11,557sqm]
6. Vehicular access/egress: Well End Road
7. Pedestrian access: Well End Road

#### **CONCLUSION**

The site is located north of Rowley Lane and east of Well End Road (plan 5309/301/C). The existing use is agricultural. The site is in 1 ownership and is predominantly flat with a very gentle incline from east to west. The site evaluation in the planning appraisal identified 23 positive site attributes and 5 negative site attributes. The site is well enclosed by existing vegetation from all directions. The site is an optimal size for an 8fe school. The site was recommended for highway appraisal.


The conclusions of the high-level transport appraisal were that there are some reservations on the suitability of increased vehicle movements along the rural section of Rowley Lane and the access onto the A1 from Holmshill Lane. A detailed review of the potential impact of school related traffic along these roads will need to be undertaken and significant improvements to the road layout will be required in order to provide a safe and suitable route, or alternatively, measures to discourage school related travel along this route. There are also potential capacity issues along Potters Lane for vehicles and cyclists, which is likely to be on a key desire line from the northern side of Borehamwood. If the concerns identified above can be mitigated to a suitable standard, then, in principle, the site may be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment. Footways along residential roads

to the west and south-west of the site are generally considered suitable. However, new crossing facilities are likely to be required. Bus accessibility to the site from Borehamwood and Elstree is reasonable, with bus stops on Alexandra Road providing access to route B3. However, existing links to the wider area would be from stops available on the B5378 Shenley Road and the A5135 Elstree Way which are over 1km from the school site. Improved accessibility between the site and the local bus stops should be considered as part of proposals. The site was ranked 6/6 for highways and accessibility due to there being no bus stop in the immediate vicinity of the site and limited potential for footway/ cycleway improvements along the desire line. Overall, the site was ranked lowest (6/6) in terms of access and highways suitability in comparison with other sites. It scored least well of all the sites in terms of providing a safe and suitable vehicular access, its location and proximity to accessible sustainable transport modes, and anticipated mitigation works.

A development principles plan (5309/322) has been prepared and is attached at Appendix 3.

It is concluded that because of the highway concerns relating to the suitability of the surrounding highway infrastructure for a school development, lack of nearby public transport infrastructure and the limited potential for highway improvements, this site should not be considered for an 8fe school unless another more sequentially preferable site cannot be identified.





**SITE BOUNDARY**  
11.74ha

**BORE 02**

**SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH**

Site identification: BORE02

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 320        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | JUNE 2020  | 1:2500 @A2 |

T: +44 (0) 1438 316 331  
planners@vincent-gorbing.co.uk  
vincent-gorbing.co.uk  
Vincent and Gorbing Limited, Sterling Court  
Norton Road, Stevenage, Hertfordshire SG1 2JY  
© Copyright Vincent and Gorbing Limited 2016.







**BORE 02**


**SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH**

Aerial photograph: BORE02

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 321        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | JUNE 2020  | 1:2500 @A2 |







- SITE BOUNDARY  
11.74ha
- BUILDING ZONE  
3.56ha
- PLAYING FIELD ZONE  
8.18ha
- SITE ACCESS


BORE 02

SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH

Development principles: BORE02

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 322        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | SEPT 2020  | 1:2500 @A2 |





KEY

- SITE BOUNDARY
- FOOTPATH
- BRIDLEWAY
- UNCLASSIFIED COUNTRY ROAD
- BYWAY OPEN TO ALL TRAFFIC
- WATERCOURSE
- POTENTIAL ACCESS LOCATION

| Rev     | Description | Date | Drawn | Checked | Apvd. |
|---------|-------------|------|-------|---------|-------|
| Project |             |      |       |         |       |

SOUTH WEST HERTS SECONDARY SCHOOLS

| Drawing Description |
|---------------------|
|---------------------|

BOREHAMWOOD SITE 02

| Drawing Number | Scale     | Date     | Drawn | Checked | Approved |
|----------------|-----------|----------|-------|---------|----------|
| ST-2995-06     | 1:5000@A3 | 17.08.20 | JJN   | SJB     |          |

| Client | Architect |
|--------|-----------|
|--------|-----------|

Do not scale off the drawing.  
Only written dimensions should be taken.  
Any discrepancies or errors should be brought to the attention of the engineer immediately.  
This document is copyright and may not be reproduced without permission of the owner.  
Ordnance Survey data contained herein is for use on this project only. Third parties involved in this project wishing to reproduce this data, for the purposes of said project, may do so on display of the following:  
© Crown Copyright All rights reserved 2015  
License No 100055466

**stomor**  
CIVIL ENGINEERING CONSULTANTS  
Suite 2, First Floor, Portmill House,  
Portmill Lane, Hitchin, Herts, SG5 1DJ  
www.stomor.com | 01462 615433 | info@stomor.com

## SOUTH -WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH: SHORTLISTED POTENTIAL SCHOOL SITE

### SITE DETAILS

|                                   |   |   |
|-----------------------------------|---|---|
| <b>Site Reference and address</b> | Borehamwood Site: 03<br>Land east of Green Street, Borehamwood<br>Site identification plan: 5309/330<br>Aerial photograph: 5309/331<br>Development principles plan: 5309/332  |   |
| <b>Site area</b>                  | 11.26 ha  |   |
| <b>Existing use/occupiers</b>     | Agricultural  |   |
| <b>Land ownership</b>             | WROTHAM PARK SETTLED ESTATES of The Estate Office, Wrotham Park, Barnet, Herts., EN5 4SB.   |   |
| <b>Site availability</b>          | Site HEL347 in HELAA 2019 Report  |   |
| <b>Brownfield Land Register</b>   | No.   |   |
| <b>Planning history</b>           | TP/98/0459 - Creation of access road to Green Street - Granted  |   |
| <b>Buildings</b>                  | None.   |   |
| <b>Adjoining uses</b>             | North:  | To the north of the site is agricultural land.                                |
|                                   | East:   | To the east of the site is agricultural land.                                 |
|                                   | South:  | To the south of the site is agricultural land.                                |
|                                   | West:   | To the west of the site are residential dwellings fronting onto Green Street. |
| <b>Topography</b>                 | The site is almost completely level.  |   |
| <b>Water courses</b>              | None.   |   |
| <b>Vegetation</b>                 | The site is formed of two agricultural field parcels. Each are bounded by hedgerows and tree belts, particularly along the northern boundary and the boundary with Green Street. There is no vegetation within the central areas of the site. |   |

### ACCESSIBILITY

|                          |  |
|--------------------------|--|
| <b>Vehicular access</b>  | Cowley Hill/Green Street bound the site to the west. The road is a classified B road with 30mph speed restriction. |
| <b>Cycle access</b>      | None.  |
| <b>Pedestrian access</b> | Green Street features footpaths on both sides of the road. There are   |

|   |  |
|---|--|
|   | informal footpaths within the site.  |
| <b>Public transport</b>                 | Stapleton Road and Stanborough Avenue bus stops are both a 0.3km walk from the site (2min). They both provide access to routes 357 (Harpenden to Borehamwood via Batford, Wheathampstead, St Albans, London Colney and Shenley) and 358 (Borehamwood – Oaklands).  |
| <b>High level transport appraisal</b>   | <p>A high-level transport appraisal prepared by Stomor Civil Engineering Consultants concludes that, in principle, it would appear that the road network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment.</p> <p>It is suggested that adequate pedestrian crossings are provided along Green Street and at suitable locations within the residential area to the south-west, in order to provide a safe and suitable route for pupils to access the school.</p> <p>The footway network along residential roads to the south-west of the site is generally considered suitable.</p> <p>Bus services in the vicinity of the site appear to be infrequent. Therefore, additional services may be required to ensure that bus access to the site is feasible.</p> <p>Due to the Covid-19 pandemic, traffic conditions at the time of writing this High-Level Assessment do not reflect former 'typical' traffic condition. Therefore, it is not possible to comment upon existing highway conditions in terms of congestion in the vicinity of the site. It is likely that any congestion issues occur at junction with London Road, which may cause school related traffic to use the network of residential roads near the school to avoid delays.</p> <p>A further review of the accidents around the Stapleton Road/Cowley Hill junction is recommended to investigate whether any safety improvements are required.</p> |
| <b>ENVIRONMENTAL IMPACT</b>             |  |
| <b>Landscape and visual impact</b>      | The site is relatively well screened from all directions.  |
| <b>Impact on residential amenities:</b> | Residential amenity to dwellings fronting onto Green Street could be affected including, noise impact, loss of sunlight/daylight, outlook etc.   |
| <b>Ecology:</b>                         | Due to the intensive agricultural nature of the site ecology is likely limited to the surrounding trees and hedgerows which may provide habitats for bats, birds and other invertebrates. A large area of woodland (local nature reserve) abuts the site to the north.   |
| <b>Noise sources</b>                    | None significant.  |
| <b>Flood risk</b>                       | Flood zone 1 – very low risk   |
| <b>Surface water flooding</b>           | Mostly very low risk – some scattered areas of low risk and patch of high risk adjacent to Green Street.   |
| <b>Groundwater source</b>               | None.  |

|                                  |  |
|----------------------------------|--|
| <b>protection area</b>           |  |
| <b>Air quality</b>               | No.  |
| <b>Minerals</b>                  | Sand and Gravel Belt.  |
| <b>Agricultural land quality</b> | 3a/3b.   |
| <b>Rights of way</b>             | Shenley footpath 004 runs along the northern boundary of the site.<br>Shenley footpath 001 starts at the southern tip of the site. |

### EXISTING PLANNING AND DESIGNATION CONSTRAINTS

|  |   |
|--|---|
| <b>Existing and emerging local plan site specific designations</b>   | Green Belt.   |
| <b>Heritage assets: archaeology</b>  | None.   |
| <b>Designated heritage assets</b>  | None.   |
| <b>Designated rural areas</b>  | None.   |
| <b>International, National and locally designated sites of importance for biodiversity and habitat sites</b> | None. A local wildlife site bounds the site to the north. |

### SITE EVALUATION

#### Positive site attributes:

1. The site is of optimal / sufficient size for 8fe
2. The site is known to be available and has been proposed for use by the landowner for C3 residential and a School.
3. The site is in single ownership.
4. The site is flat and re-grading would be minimal.
5. Vehicular access could likely be achieved from Green Street with suitable mitigation/improvements.
6. Pedestrian/cycle access could likely be achieved from Green Street with suitable mitigation/improvements.
7. The site lies adjacent/within 400m walking distance of bus stops and bus routes.
8. Site development would not be exposed to long distance views in the wider landscape.
9. The site lies adjacent to the urban area of Borehamwood.
10. There would be no impacts on preserved trees.
11. The site is not at risk of flooding [subject to further investigations].
12. The site is not located near any noise sources.
13. The site lies outside an AQMA.



14. The site is not in an Area of Archaeological Importance.
15. There would be no impacts on designated heritage assets.
16. The site is not in a designated rural area.
17. The site does not have any international, national or local wildlife, habitat or biodiversity designations.
18. The site does not have any local plan allocation.
19. The site is not an identified HELAA site.
20. The site has a single landowner.

#### **Negative site attributes:**

1. The site lies in the Green Belt.
2. There is potential for more than minor harm to occur to ecology.
3. The site lies in a Minerals Consultation Area.
4. The site has moderate-good grade agricultural land classification [if relevant].
5. The site is partially traversed by rights of way.
6. The site is split into two field parcels separated by mature vegetation. It is likely that this would result in poor supervision/safeguarding visibility.

#### **SITE LAYOUT PRINCIPLES**

A BB103 compliant 8fe secondary school site could be accommodated on this site:

1. Development principles plan 5309/332
2. Total site area: [11.26 ha]
3. Build zone: [3.57 ha]
4. Playing Field zone: [7.69 ha]
5. Building footprint: [11,557 sqm]
6. Vehicular access/egress: [Green Street]
7. Pedestrian access: [Green Street]

#### **CONCLUSION**

The site is located east of Green Street, Borehamwood (plan 5309/301/B) extending north-east away from Green Street. The existing use is agricultural. The site is in 1 ownership and is flat. The site is an optimal size for an 8fe secondary school. The site was recommended for highway appraisal.

The conclusions of the highway appraisal were that in principle, it would appear that the road network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment. It is suggested that adequate pedestrian crossings are provided along Green Street and at suitable locations within the residential area to the south-west, in order to provide a safe and suitable route for pupils to access the school. The footway network along residential roads to the south-west of the site is generally considered suitable. Bus services in the vicinity of the site appear to be infrequent. Therefore, additional services may be required to ensure that bus access to the site is feasible. The site was ranked 4/6 in terms of access and highways suitability in comparison with other sites. Whilst it scored high on providing a safe and suitable vehicular access, it scored less favourably in terms of its location and access by sustainable forms of transportation.


A development principles plan (5309/332) has been prepared and is attached at Appendix 3. The plan shows the disposition of the building zone, playing fields and the optimal point of vehicular



access to the site (based on highway appraisal conclusions). The tree line in the centre of the site splitting the 2 land parcels could be retained although there would be poor supervision and intervisibility between the school building and the playing fields.

It is concluded that because of the poor intervisibility between the two land parcels and the comparatively undesirable location of the site in terms of its access by sustainable forms of transport, this site should not be considered for an 8fe school unless another more sequentially preferable site cannot be identified.





SITE BOUNDARY  
11.26ha

OTHER POTENTIAL SITES

**SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH**

Site identification: BORE03

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 330        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | JUNE 2020  | 1:2500 @A2 |





**BORE 03**


**SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH**



Aerial photograph: BORE03

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 331        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | JUNE 2020  | 1:2500 @A2 |








-  SITE BOUNDARY  
11.26ha
-  BUILDING ZONE  
3.57ha
-  PLAYING FIELD ZONE  
7.69ha
-  SITE ACCESS

## SOUTH WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH

Development principles: BORE03

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 332        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | SEPT 2020  | 1:2500 @A2 |





KEY

SITE BOUNDARY

FOOTPATH

BRIDLEWAY

BYWAY OPEN TO ALL TRAFFIC

WATERCOURSE

POTENTIAL ACCESS LOCATION

SITE 03

SITE 04

SITE 05

Rev

Description

Date

Drawn

Checked

Apvd.

Project

SOUTH WEST HERTS SECONDARY SCHOOLS

Drawing Description

BOREHAMWOOD SITE 3,4,5

Drawing Number

ST-2995-13

Scale

1:5000@A3

Date

17.08.20

Drawn

JJN

Checked

NJM

Approved

SJB

Client

Architect

Do not scale off the drawing.  
Only written dimensions should be taken.  
Any discrepancies or errors should be brought  
to the attention of the engineer immediately.  
This document is copyright and may not be  
reproduced without permission of the owner.

Ordnance Survey data contained herein is for  
use on this project only. Third parties involved  
in this project wishing to reproduce this data,  
for the purposes of said project, may do so on  
display of the following:

© Crown Copyright All rights reserved 2015  
License No 100055466

stomor

CIVIL ENGINEERING CONSULTANTS

Suite 2, First Floor, Portmill House,  
Portmill Lane, Hitchin, Herts, SG5 1DJ  
www.stomor.com | 01462 615433 | info@stomor.com

## SOUTH -WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH: SHORTLISTED POTENTIAL SCHOOL SITE

### SITE DETAILS

|                                   |   |  |
|-----------------------------------|---|--|
| <b>Site Reference and address</b> | Borehamwood Site: 04<br>Land east of Green Street, Borehamwood<br>Site identification plan: 5309/340<br>Aerial photograph: 5309/341<br>Development principles plan: [5309/342]  |  |
| <b>Site area</b>                  | 10.73 ha  |  |
| <b>Existing use/occupiers</b>     | Agricultural  |  |
| <b>Land ownership</b>             | WROTHAM PARK SETTLED ESTATES of The Estate Office, Wrotham Park, Barnet, Herts., EN5 4SB.<br>&<br>JOHN MOORE of 5 Anderson Road, Shenley, Radlett, Herts., and<br>HERBERT JAMES MARTIN of 1 The Pines, Rectory Lane, Shenley, Herts.<br>&<br>VILLA SCALABRINI (Co. Regn. No. 04750130) of Villa Scalabrini, Green Street, Shenley, Radlett WD7 9BB. |  |
| <b>Site availability</b>          | The northern part of the site is unknown. The southern half is available and is listed as site HEL347 in the HELAA 2019 report.   |  |
| <b>Brownfield Land Register</b>   | No.   |  |
| <b>Planning history</b>           | None.   |  |
| <b>Buildings</b>                  | None.   |  |
| <b>Adjoining uses</b>             | North:  | To the north of the site is agricultural land and Villa Scalabrini, a retirement home. |
|                                   | East:   | To the east of the site is agricultural land.  |
|                                   | South:  | To the south of the site is agricultural land.   |
|                                   | West:   | To the west of the site are residential dwellings fronting onto Green Street.          |
| <b>Topography</b>                 | The site is almost completely level. There is a slight incline from south-east to north-west.   |  |
| <b>Water courses</b>              | None.   |  |
| <b>Vegetation</b>                 | The site is formed of three agricultural field parcels. Each are bounded by hedgerows and tree belts. There is no vegetation within the central   |  |

|   |  |
|---|--|
|   | areas of the site, although the hedgerow between fields is relatively dense.   |
| <b>ACCESSIBILITY</b>                    |  |
| <b>Vehicular access</b>                 | Cowley Hill/Green Street bound the site to the west. The road is a classified B road with 30mph speed restriction.   |
| <b>Cycle access</b>                     | None.  |
| <b>Pedestrian access</b>                | Green Street features footpaths on both sides of the road. There are informal footpaths within and around the site.  |
| <b>Public transport</b>                 | Stapleton Road bus stop is a 0.1km walk from the site (1min) and Stanborough Avenue bus stop is 0.3km. They both provide access to routes 357 (Harpenden to Borehamwood via Watford, Wheathampstead, St Albans, London Colney and Shenley) and 358 (Borehamwood – Oaklands).   |
| <b>High level transport appraisal</b>   | <p>A high-level transport appraisal prepared by Stomor Civil Engineering Consultants concludes that, in principle, it would appear that the road network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment.</p> <p>It is suggested that adequate pedestrian crossings are provided along Green Street and at suitable locations within the residential area to the south-west, in order to provide a safe and suitable route for pupils to access the school.</p> <p>The footway network along residential roads to the south-west of the site is generally considered suitable.</p> <p>Bus services in the vicinity of the site appear to be infrequent. Therefore, additional services may be required to ensure that bus access to the site is feasible.</p> <p>Due to the Covid-19 pandemic, traffic conditions at the time of writing this High-Level Assessment do not reflect former 'typical' traffic condition. Therefore, it is not possible to comment upon existing highway conditions in terms of congestion in the vicinity of the site. It is likely that any congestion issues occur at junction with London Road, which may cause school related traffic to use the network of residential roads near the school to avoid delays.</p> <p>A further review of the accidents around the Stapleton Road/Cowley Hill junction is recommended to investigate whether any safety improvements are required.</p> |
| <b>ENVIRONMENTAL IMPACT</b>             |  |
| <b>Landscape and visual impact</b>      | The site is relatively well screened from all directions.  |
| <b>Impact on residential amenities:</b> | Residential amenity to dwellings fronting onto Green Street could be affected including, noise impact, loss of sunlight/daylight, outlook etc.   |
| <b>Ecology:</b>                         | Due to the intensive agricultural nature of the site and mowing regime in  |



|   |   |
|---|---|
|   | grassed areas, ecology is likely limited to the surrounding trees and hedgerows which may provide habitats for bats, birds and other invertebrates. As there is a significant amount of vegetation on site, the ecological value could be high. |
| <b>Noise sources</b>                      | None significant.   |
| <b>Flood risk</b>                         | Flood zone 1 – very low risk  |
| <b>Surface water flooding</b>             | Mostly very low risk – some scattered areas of low risk and patch of high risk adjacent to Green Street.  |
| <b>Groundwater source protection area</b> | None.   |
| <b>Air quality</b>                        | No.   |
| <b>Minerals</b>                           | Sand and Gravel Belt.   |
| <b>Agricultural land quality</b>          | 3a/3b.  |
| <b>Rights of way</b>                      | Shenley footpath 004 runs through the centre of the site. Shenley footpath 001 starts at the southern tip of the site.  |

### EXISTING PLANNING AND DESIGNATION CONSTRAINTS

|  |   |
|--|---|
| <b>Existing and emerging local plan site specific designations</b>   | Green Belt.   |
| <b>Heritage assets: archaeology</b>  | None.   |
| <b>Designated heritage assets</b>  | None.   |
| <b>Designated rural areas</b>  | None.   |
| <b>International, National and locally designated sites of importance for biodiversity and habitat sites</b> | None. A local wildlife site is just east of the site. |

### SITE EVALUATION

#### Positive site attributes:

1. The site is of optimal / sufficient size for 7fe
2. The site is flat and re-grading would be minimal.
3. Vehicular access could likely be achieved from Green Street with suitable mitigation/improvements.
4. Pedestrian/cycle access could likely be achieved from Green Street with suitable mitigation/improvements.
5. The site lies adjacent/within 400m walking distance of bus stops and bus routes.



6. Site development would not be exposed to long distance views in the wider landscape.
7. The site lies adjacent to the urban area of Borehamwood.
8. There would be no impacts on preserved trees.
9. The site is not at risk of flooding [subject to further investigations].
10. The site is not located near any noise sources.
11. The site lies outside an AQMA.
12. The site is not in an Area of Archaeological Importance.
13. There would be no impacts on designated heritage assets.
14. The site is not in a designated rural area.
15. The site does not have any international, national or local wildlife, habitat or biodiversity designations.
16. The site does not have any local plan allocation.
17. The site is not an identified SHELAA site.
18. The site has a single landowner.

#### **Negative site attributes:**

1. The whole site is not known to be available.
2. The site is not in single ownership.
3. The site lies in the Green Belt.
4. The site lies in a Minerals Consultation Area.
5. The site has moderate-good grade agricultural land classification [if relevant].
6. The site is traversed by rights of way.
7. A significant amount of hedgerow/tree belt would need to be removed to accommodate the development.
8. There would likely be more than minor ecological impact [subject to further investigations].

#### **SITE LAYOUT PRINCIPLES**

A BB103 compliant 8fe secondary school site could be accommodated on this site:

1. Development principles plan 5309/342
2. Total site area: [10.73 ha]
3. Build zone: [3.56 ha]
4. Playing Field zone: [7.17 ha]
5. Building footprint: [11,557 sqm]
6. Vehicular access/egress: [Green Street]
7. Pedestrian access: [Green Street]

#### **CONCLUSION**

The site is located east of Green Street, Borehamwood (plan 5309/301 B) extending north-west in parallel to Green Street. The existing use is agricultural, and the site is in 3 ownerships. The site


evaluation identified 20 positive attributes and 9 negative site attributes. The site is an optimal size for an 8fe secondary school. The site was recommended for high level transport appraisal.

The conclusions of the high level transport appraisal were that in principle, it would appear that the road network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment. It is suggested that adequate pedestrian crossings are provided along Green Street and at suitable locations within the residential area to the south-west, in order to provide a safe and suitable route for pupils to access the school. The footway network along residential roads to the south-west of the site is generally considered suitable. Bus services in the vicinity of the site appear to be infrequent. Therefore, additional services may be required to ensure that bus access to the site is feasible. The site was ranked 3/6 in terms of access and highways suitability. Whilst it scored high on providing a safe and suitable vehicular access, it scored less favourably in terms of its location and access by sustainable forms of transportation.

A development principles plan (5309) has been prepared and is attached at Appendix 3. The plan shows the disposition of the building zone, playing fields and the optimal point of vehicular access to the site (based on highway appraisal conclusions). The location of the playing fields would require the removal of a significant tree belt in the centre of the site.

It is concluded that because of the need to remove mature vegetation on site and the comparatively undesirable location of the site in terms of its access by sustainable forms of transportation, this site should not be considered for an 8fe school unless another more sequentially preferable site cannot be identified.





**SITE BOUNDARY**  
10.73ha

**OTHER POTENTIAL SITES**

## SOUTH WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH

Site identification: BORE04

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 340        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | JUNE 2020  | 1:2500 @A2 |

T: +44 (0) 1438 316 331  
planners@vincent-gorbing.co.uk  
vincent-gorbing.co.uk

Vincent and Gorbing Limited, Sterling Court  
Norton Road, Stevenage, Hertfordshire SG1 2JY

© Copyright Vincent and Gorbing Limited 2016.








**SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH**

Aerial photograph: BORE04

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 341        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | JUNE 2020  | 1:2500 @A2 |








- SITE BOUNDARY  
10.73ha
- BUILDING ZONE  
3.56ha
- PLAYING FIELD ZONE  
7.17ha
- SITE ACCESS
- DIVERTED FOOTPATH

**SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH**










Development principles: BORE04

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 342        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | SEPT 2020  | 1:2500 @A2 |





## KEY

-  SITE BOUNDARY
-  FOOTPATH
-  BRIDLEWAY
-  BYWAY OPEN TO ALL TRAFFIC
-  WATERCOURSE
-  POTENTIAL ACCESS LOCATION
-  SITE 03
-  SITE 04
-  SITE 05

| Rev     | Description | Date | Drawn | Checked | Apvd. |
|---------|-------------|------|-------|---------|-------|
| Project |             |      |       |         |       |

SOUTH WEST HERTS SECONDARY SCHOOLS

|                     |  |
|---------------------|--|
| Drawing Description |  |
|---------------------|--|

BOREHAMWOOD SITE 3,4,5

|                |           |          |       |         |          |
|----------------|-----------|----------|-------|---------|----------|
| Drawing Number | Scale     | Date     | Drawn | Checked | Approved |
| ST-2995-13     | 1:5000@A3 | 17.08.20 | JJN   | NJM     | SJB      |

|        |           |
|--------|-----------|
| Client | Architect |
|--------|-----------|

*Do not scale off the drawing.  
Only written dimensions should be taken.  
Any discrepancies or errors should be brought  
to the attention of the engineer immediately.  
This document is copyright and may not be*

Ordinance Survey data contained herein is for use on this project only. Third parties involved in this project wishing to reproduce this data, for the purposes of said project, may do so on display of the following:

© Crown Copyright All rights reserved 2015  
License No 100055466

**stomor**  
CIVIL ENGINEERING CONSULTANTS

Suite 2, First Floor, Portmill House,  
Portmill Lane, Hitchin, Herts, SG5 1DJ

www.stomor.com | 01462 615433 | info@stomor.com



## SOUTH -WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH: SHORTLISTED POTENTIAL SCHOOL SITE

### SITE DETAILS

|                                   |  |  |
|-----------------------------------|--|--|
| <b>Site Reference and address</b> | Borehamwood Site: BORE05<br>Land east of Green Street, Borehamwood<br>Site identification plan: 5309/350<br>Aerial photograph: 5309/351<br>Development principles plan: [5309/352]   |  |
| <b>Site area</b>                  | 11 ha  |  |
| <b>Existing use/occupiers</b>     | Agricultural   |  |
| <b>Land ownership</b>             | HERTFORDSHIRE COUNTY COUNCIL of County Hall, Hertford SG13 8DE and of DX145781, Hertford 4<br>&<br>JOHN MOORE of 5 Anderson Road, Shenley, Radlett, Herts., and<br>HERBERT JAMES MARTIN of 1 The Pines, Rectory Lane, Shenley, Herts.<br>&<br>VILLA SCALABRINI (Co. Regn. No. 04750130) of Villa Scalabrini, Green Street, Shenley, Radlett WD7 9BB. |  |
| <b>Site availability</b>          | Unknown  |  |
| <b>Brownfield Land Register</b>   | No.  |  |
| <b>Planning history</b>           | None.  |  |
| <b>Buildings</b>                  | None.  |  |
| <b>Adjoining uses</b>             | North:   | To the north of the site is agricultural land and Villa Scalabrini, a retirement home. |
|                                   | East:  | To the east of the site is an area of woodland which is a local nature reserve.        |
|                                   | South:   | To the south of the site is agricultural land.   |
|                                   | West:  | To the west of the site are residential dwellings fronting onto Green Street.          |
| <b>Topography</b>                 | The site is almost completely level. There is a slight incline from south-east to north-west.  |  |
| <b>Water courses</b>              | None.  |  |
| <b>Vegetation</b>                 | The site is formed of three agricultural field parcels. Each are bounded by hedgerows and tree belts. There is no vegetation within the central  |  |

|   |  |
|---|--|
|   | areas of the site, although the hedgerow between fields is relatively dense.   |
| <b>ACCESSIBILITY</b>                    |  |
| <b>Vehicular access</b>                 | Cowley Hill/Green Street bound the site to the west. The road is a classified B road with 30mph speed restriction.   |
| <b>Cycle access</b>                     | None.  |
| <b>Pedestrian access</b>                | Green Street features footpaths on both sides of the road. There are informal footpaths within and around the site.  |
| <b>Public transport</b>                 | Stapleton Road bus stop is a 0.1km walk from the site (1min) and Stanborough Avenue bus stop is 0.3km. They both provide access to routes 357 (Harpenden to Borehamwood via Batford, Wheathampstead, St Albans, London Colney and Shenley) and 358 (Borehamwood – Oaklands).   |
| <b>High level transport appraisal</b>   | <p>A high-level transport appraisal prepared by Stomor Civil Engineering Consultants concludes that, in principle, it would appear that the road network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment.</p> <p>It is suggested that adequate pedestrian crossings are provided along Green Street and at suitable locations within the residential area to the south-west, in order to provide a safe and suitable route for pupils to access the school.</p> <p>The footway network along residential roads to the south-west of the site is generally considered suitable.</p> <p>Bus services in the vicinity of the site appear to be infrequent. Therefore, additional services may be required to ensure that bus access to the site is feasible.</p> <p>Due to the Covid-19 pandemic, traffic conditions at the time of writing this High-Level Assessment do not reflect former 'typical' traffic condition. Therefore, it is not possible to comment upon existing highway conditions in terms of congestion in the vicinity of the site. It is likely that any congestion issues occur at junction with London Road, which may cause school related traffic to use the network of residential roads near the school to avoid delays.</p> <p>A further review of the accidents around the Stapleton Road/Cowley Hill junction is recommended to investigate whether any safety improvements are required.</p> |
| <b>ENVIRONMENTAL IMPACT</b>             |  |
| <b>Landscape and visual impact</b>      | The site is relatively well screened from all directions.  |
| <b>Impact on residential amenities:</b> | Residential amenity to dwellings fronting onto Green Street could be affected including, noise impact, loss of sunlight/daylight, outlook etc. Villa Scallabrini, a retirement home, is situated north of the site. Noise impact could be particularly detrimental to this use.  |



|   |   |
|---|---|
| <b>Ecology:</b>                           | Due to the intensive agricultural nature of the site and mowing regime in grassed areas, ecology is likely limited to the surrounding trees and hedgerows which may provide habitats for bats, birds and other invertebrates. A large area of woodland (a local nature reserve) is just east of the site. |
| <b>Noise sources</b>                      | None significant.   |
| <b>Flood risk</b>                         | Flood zone 1 – very low risk  |
| <b>Surface water flooding</b>             | Mostly very low risk – however there are areas of low-high risk in the eastern part of the site.  |
| <b>Groundwater source protection area</b> | None.   |
| <b>Air quality</b>                        | No.   |
| <b>Minerals</b>                           | Sand and Gravel Belt.   |
| <b>Agricultural land quality</b>          | 3a/3b.  |
| <b>Rights of way</b>                      | Shenley footpath 004 runs along the southern boundary of the site.  |

### EXISTING PLANNING AND DESIGNATION CONSTRAINTS

|  |   |
|--|---|
| <b>Existing and emerging local plan site specific designations</b>   | Green Belt.   |
| <b>Heritage assets: archaeology</b>  | None.   |
| <b>Designated heritage assets</b>  | None.   |
| <b>Designated rural areas</b>  | None.   |
| <b>International, National and locally designated sites of importance for biodiversity and habitat sites</b> | None. A local wildlife site is just east of the site. |

### SITE EVALUATION

#### Positive site attributes:

1. The site is of optimal / sufficient size for 8fe
2. The site is flat and re-grading would be minimal.
3. Vehicular access could likely be achieved from Green Street with suitable mitigation/improvements.
4. Pedestrian/cycle access could likely be achieved from Green Street with suitable mitigation/improvements.
5. The site lies adjacent/within 400m walking distance of bus stops and bus routes.



6. Site development would not be exposed to long distance views in the wider landscape.
7. The site lies adjacent to the urban area of Borehamwood.
8. There would be no impacts on preserved trees.
9. The site is not located near any noise sources.
10. The site lies outside an AQMA.
11. The site is not in an Area of Archaeological Importance.
12. There would be no impacts on designated heritage assets.
13. The site is not in a designated rural area.
14. The site does not have any international, national or local wildlife, habitat or biodiversity designations.
15. The site does not have any local plan allocation.
16. The site is not an identified HELAA site.

#### **Negative site attributes:**

1. The site is not known to be available.
2. The site is not in single ownership.
3. The site lies in the Green Belt.
4. There is potential for more than minor harm to occur to ecology.
5. The eastern part of the site is at risk of surface water flooding.
6. The site lies in a Minerals Consultation Area.
7. The site has moderate-good grade agricultural land classification [if relevant].
8. The site is traversed by rights of way.
9. A significant amount of hedgerow/tree belt would need to be removed to accommodate the development. If this is not removed there would be poor intervisibility and supervision.

#### **SITE LAYOUT PRINCIPLES**

A BB103 compliant 8fe secondary school site could be accommodated on this site:

1. Development principles plan 5309/352
2. Total site area: [11.00 ha]
3. Build zone: [3.60 ha]
4. Playing Field zone: [7.40 ha]
5. Building footprint: [11,557 sqm]
6. Vehicular access/egress: [Green Street]
7. Pedestrian access: [Green Street]

#### **CONCLUSION**

The site is located east of Green Street, Borehamwood (plan 5309/301/C) extending north-east away from Green Street. The existing use is agricultural, and the site is in 3 ownerships, including partly owned by Hertfordshire County Council. The site is an optimal size for an 8fe secondary school. The site was recommended for transport appraisal.

The conclusions of the transport appraisal were that in principle, it would appear that the road




network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment. It is suggested that adequate pedestrian crossings are provided along Green Street and at suitable locations within the residential area to the south-west, in order to provide a safe and suitable route for pupils to access the school. The footway network along residential roads to the south-west of the site is generally considered suitable. Bus services in the vicinity of the site appear to be infrequent. Therefore, additional services may be required to ensure that bus access to the site is feasible. The site was ranked 5/6 in terms of access and highways suitability. Whilst it scored high on providing a safe and suitable vehicular access, it scored less favourably in terms of its location and access by sustainable forms of transportation and issues with parking on Green Street.

A development principles plan (5309/352) has been prepared and is attached at Appendix 3. The plan shows the disposition of the building zone, playing fields and the optimal point of vehicular access to the site (based on highway appraisal conclusions). The playing fields would be split into two parcels unless the tree line between them is removed. The tree lines around the building zone boundaries to the playing fields could be retained although there would be poor supervision and intervisibility between the school building and the playing fields.

It is concluded that because of the need to remove mature vegetation on site, the poor supervision and intervisibility between the building zone and the playing fields and the relatively undesirable location of the site in terms of its access by sustainable forms of transportation, this site should not be considered for an 8fe school unless another more sequentially preferable site cannot be identified.





**SITE BOUNDARY**  
11.00ha

**OTHER POTENTIAL SITES**

**SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH**

Site identification: BORE05

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 350        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | JUNE 2020  | 1:2500 @A2 |

T: +44 (0) 1438 316 331  
planners@vincent-gorbing.co.uk  
vincent-gorbing.co.uk

Vincent and Gorbing Limited, Sterling Court  
Norton Road, Stevenage, Hertfordshire SG1 2JY

© Copyright Vincent and Gorbing Limited 2016.

**VG**





**BORE 05**


**SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH**

Aerial photograph: BORE05

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 351        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | JUNE 2020  | 1:2500 @A2 |








- SITE BOUNDARY  
11.00ha
- BUILDING ZONE  
3.60ha
- PLAYING FIELD ZONE  
7.40ha
- SITE ACCESS

**SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH**

Development principles: BORE05

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 352        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | SEPT 2020  | 1:2500 @A2 |





KEY

SITE BOUNDARY

FOOTPATH

BRIDLEWAY

BYWAY OPEN TO ALL TRAFFIC

WATERCOURSE

POTENTIAL ACCESS LOCATION

SITE 03

SITE 04

SITE 05

Rev

Description

Date

Drawn

Checked

Apvd.

Project

SOUTH WEST HERTS SECONDARY SCHOOLS

Drawing Description

BOREHAMWOOD SITE 3,4,5

Drawing Number

ST-2995-13

Scale

1:5000@A3

Date

17.08.20

Drawn

JJN

Checked

NJM

Approved

SJB

Client

Architect

Do not scale off the drawing.  
Only written dimensions should be taken.  
Any discrepancies or errors should be brought  
to the attention of the engineer immediately.  
This document is copyright and may not be  
reproduced without permission of the owner.

Ordnance Survey data contained herein is for  
use on this project only. Third parties involved  
in this project wishing to reproduce this data,  
for the purposes of said project, may do so on  
display of the following:

© Crown Copyright All rights reserved 2015  
License No 100055466

stomor

CIVIL ENGINEERING CONSULTANTS

Suite 2, First Floor, Portmill House,  
Portmill Lane, Hitchin, Herts, SG5 1DJ

www.stomor.com

01462 615433

info@stomor.com



## SOUTH -WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH: SHORTLISTED POTENTIAL SCHOOL SITE

### SITE DETAILS

|                                   |   |   |
|-----------------------------------|---|---|
| <b>Site Reference and address</b> | Borehamwood Site: BORE06<br>Land north of Allum Lane, Elstree<br>Site identification plan: [5309/360]<br>Aerial photograph: [5309/361]  |   |
| <b>Site area</b>                  | 10.96 ha  |   |
| <b>Existing use/occupiers</b>     | Grassland / Agricultural  |   |
| <b>Land ownership</b>             | ELSTREE GOLF AND COUNTRY CLUB LIMITED of 172/174 Nantwich Road, Crewe, Cheshire.<br>&<br>MARGARET LOIS ROSE of South Medburn Farm, Watling Street, Elstree, Herts.                                |   |
| <b>Site availability</b>          | The availability of most of the site is unknown. The eastern part of the site forms part of the Radlett Park Golf Club which is available and identified as site HEL514 in the HELAA 2019 Report. |   |
| <b>Brownfield Land Register</b>   | No  |   |
| <b>Planning history</b>           | None.   |   |
| <b>Buildings</b>                  | None.   |   |
| <b>Adjoining uses</b>             | North:  | To the north of the site is agricultural land and the Radlett Park Golf Club.                         |
|                                   | East:   | To the east of the site are residential areas of Borehamwood/Elstree,                                 |
|                                   | South:  | The site is bounded to the south by Allum Lane. Beyond this is a stables and a cemetery.              |
|                                   | West:   | To the west of the site are allotment grounds and residential dwellings fronting onto Watling Street. |
| <b>Topography</b>                 | The site inclines moderately to the east.   |   |
| <b>Water courses</b>              | OS maps show a small water course running through the site. This was not evident during the site visit.   |   |
| <b>Vegetation</b>                 | The site is bounded by hedgerow and trees. There are mature trees scattered throughout the central areas of the site and a denser wooded area between the golf course and the rest of the site.   |   |

### ACCESSIBILITY



|                                       |  |
|---------------------------------------|--|
| <b>Vehicular access</b>               | Allum Lane (classified B road) bounds the site to the south. There is a 30mph limit. The junction with Watling Street was noticeably busy.   |
| <b>Cycle access</b>                   | None.  |
| <b>Pedestrian access</b>              | There is a pedestrian footpath on the southern side of Allum Lane. There is a public right of way running through the site.  |
| <b>Public transport</b>               | Elstree Hill North bus stop is directly adjacent to the south-western corner of the site. This is served by route 107 (with connections between New Barnet and Edgware), 306 (Watford-Borehamwood) and 823 (Garston – Borehamwood) |
| <b>High level transport appraisal</b> | A high-level transport appraisal was not recommended.  |

## ENVIRONMENTAL IMPACT

|   |   |
|---|---|
| <b>Landscape and visual impact</b>        | The site is relatively well enclosed although long distance views may be possible from the north where there is less dense vegetative screening.  |
| <b>Impact on residential amenities:</b>   | There is potential for noise/light impact to occur to dwellings fronting onto Watling Street to the west and The Stables to the east.   |
| <b>Ecology:</b>                           | There are a number of mature trees on site which likely provide habitats for bird, bats and other invertebrate. At the time of the site visit much of the site was covered in long grass which could provide habitats to lizards and other small mammals. |
| <b>Noise sources</b>                      | Some noise may arise from Allum Lane / Watling Street.  |
| <b>Flood risk</b>                         | Flood Zone 1 – very low risk  |
| <b>Surface water flooding</b>             | A strip of land at high risk of surface water flooding runs along the western boundary of the site. There is also a strip of low-medium risk along the eastern boundary of the site. Allum Lane is known locally to flood.                                |
| <b>Groundwater source protection area</b> | None.   |
| <b>Air quality</b>                        | None.   |
| <b>Minerals</b>                           | None.   |
| <b>Agricultural land quality</b>          | 3a/3b   |
| <b>Rights of way</b>                      | Elstree and Borehamwood Footpath 057 runs along the western boundary of the site.   |

## EXISTING PLANNING AND DESIGNATION CONSTRAINTS

|  |   |
|--|---|
| <b>Existing and emerging local plan site specific designations</b> | Green Belt<br>Partially - HELAA Site HEL514 |
|--|---|



|  |   |
|--|---|
|  |   |
| <b>Heritage assets: archaeology</b>  | A small part of the site is designated as an area of archaeological significance.   |
| <b>Designated heritage assets</b>  | Aldenham House Registered Park and Garden is situated just west of the site. There is also a Grade II listed barn to the east/south of the site at Nicoll Farm. |
| <b>Designated rural areas</b>  | None.   |
| <b>International, National and locally designated sites of importance for biodiversity and habitat sites</b> | None.   |

## SITE EVALUATION

### Positive site attributes:

1. The site is of optimal / sufficient size for 8fe
2. Vehicular access could potentially be achieved from Allum Lane with suitable mitigation/improvements.
3. Pedestrian/cycle access could potentially be achieved from Allum Lane with suitable mitigation/improvements.
4. The site lies adjacent/within 400m walking distance of bus stops and bus routes.
5. The site lies adjacent to the urban area of Borehamwood/Elstree.
6. There would be no impacts on preserved trees.
7. There would be minor ecological impact [subject to further investigations].
8. The site is not located near any significant noise sources.
9. The site lies outside an AQMA.
10. The site does not lie in a Minerals Consultation Area.
11. The site is not in a designated rural area.
12. The site does not have any international, national or local wildlife, habitat or biodiversity designations.
13. The site does not lie in a Minerals Consultation Area.
14. The site is does not have any local plan allocation.

### Negative site attributes:

1. The site is in more than one ownership.
2. Most of the site is not known to be available.
3. The site is sloping and re-grading would be required.
4. Site development may be exposed to long distance views in the wider landscape.
5. The site has significant areas of vegetation that would require removal to accommodate a secondary school.
6. The site is at risk of surface water flooding [subject to further investigations].



7. The site lies in the Green Belt.
8. The site is in an Area of Archaeological Importance.
9. There may be impacts on designated heritage assets.
10. The site does have an HELAA allocation [HEL514].
11. The site has moderate-good grade agricultural land classification [if relevant].
12. The site is traversed by rights of way.
13. The site more than one landowner/is not in the ownership of HCC.

## SITE LAYOUT PRINCIPLES

A BB103 compliant 8fe secondary school site could not be accommodated on this site.

## CONCLUSION

The site is located north of Allum Lane, Borehamwood (plan 5309/301/B). The existing uses are grassland and part of Radlett Park Golf Club which is identified as site HEL514 in the HELAA 2019 Report. The site is in 2 ownerships. The site evaluation identified 16 positive site attributes and 15 negative site attributes. The site is an optimal size for an 8fe secondary school.

The site is moderately sloped, inclining to the east meaning which would necessitate regrading. Site development may be exposed to long distance views in the wider landscape. There is a significant area of large mature trees within the site that would require removal to accommodate the development. Part of the site is in an area of archaeological importance adding a further potential constraint. Whilst the site is in the HELLA as a potential housing site it is still in use as a golf course.

For the above reasons, the site was too heavily constrained and was not therefore recommended for a high-level transport appraisal or for comparative assessment with other sites.









**BORE 06**

**SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH**

Aerial photograph: BORE06

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 361        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | JUNE 2020  | 1:2500 @A2 |





## SOUTH -WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH: SHORTLISTED POTENTIAL SCHOOL SITE

### SITE DETAILS

|                                   |  |  |
|-----------------------------------|--|--|
| <b>Site Reference and address</b> | Borehamwood: Site BORE07<br>Land south of Allum Lane, Borehamwood<br>Site identification plan: 5309/370<br>Aerial photograph: 5309/371<br>Development principles plan: [5309/372]  |  |
| <b>Site area</b>                  | 16.00 ha   |  |
| <b>Existing use/occupiers</b>     | Agricultural pasture   |  |
| <b>Land ownership</b>             | ANNE JEANETTE MATTOCK of 209 Edgwarebury Lane, Edgware, Middx HA8 8QJ and DAVID JOHN BIRN of Trayman, 189 Stoke Newington High Street, London N16 0LH.<br>&<br>PETER GEORGE SUTTON FARROW of Maydene House, New Road, Prestwood, Great Missenden HP16 0PX and NOEL THOMAS FARROW of Wellbrook Place, Hammer Lane, Vines Cross, Heathfield TN21 9HF and ALEXANDER ERIC BENTLEY FARROW of 19 Shipbourne Road, Tonbridge TN10 3DN and ANDREW ROBERT FARROW of 2 Canterbury Road, Urmston, Manchester M41 7AX.<br>&<br>MOHAMMED AKMAL of Oaklands, Lime Grove, London N20 8PX.<br><PENDING OWNERSHIP UPDATE> |  |
| <b>Site availability</b>          | Site in HEL393 in HELAA 2019   |  |
| <b>Brownfield Land Register</b>   | No.  |  |
| <b>Planning history</b>           | TP/91/0641 - Retention of fill material laid along trackway and on adjacent land to form hardstanding – Refused<br><br>TP/88/0749 Outline application for erection of 2 storey single family dwellings. Density to be determined (REFUSED)   |  |
| <b>Buildings</b>                  | There are a couple of single storey structures to the south of the cemetery used as agricultural storage.  |  |
| <b>Adjoining uses</b>             | North:   | The site is bounded to the north by Allum Lane, beyond which are residential dwellings, agricultural land and Radlett Golf Course. |
|                                   | East:  | To the east are residential areas of Borehamwood/Elstree.  |
|                                   | South:   | To the south of the site is woodland.  |



|                                |   |   |
|--------------------------------|---|---|
|                                | West:   | To the west of the site is Allum Lane Cemetery, a recycling centre and stables. |
| Topography                     | The site is gently undulating. There is a gentle slope upwards towards the centre of the site and the ground slopes downwards on either side to east and west.  |   |
| Water courses                  | No water courses were evident during the site visit. However, Google Maps shows two bands of water within the southern part of the site.  |   |
| Vegetation                     | There is a low hedgerow bounding the site with Allum Lane. To the west, bounding the cemetery, is a dense tree belt. A row of trees begins at the centre of the northern field boundary and extends around the eastern part of the site. There are trees/hedges demarking the field boundaries of the site, although within the open areas, vegetation is relatively sparse. To the south of the site is a large area of woodland. There are TPO trees to the eastern part of the site.   |   |
| ACCESSIBILITY                  |   |   |
| Vehicular access               | Allum Lane (classified B road) bounds the site to the north. There is a 30mph limit. The junction with Watling Street was noticeably busy.  |   |
| Cycle access                   | None.   |   |
| Pedestrian access              | There is a public footpath on the southern side of Allum Lane.  |   |
| Public transport               | Knowl Lane bus stop is less than 50m away from the site (<1 minute walk). This is served by route 107 (with connections between New Barnet and Edgware), 306 (Watford-Borehamwood) and 823 (Garston – Borehamwood)  |   |
| High level transport appraisal | <p>A high-level transport appraisal prepared by Stomor Civil Engineering Consultants concludes that, in principle, it would appear that the road network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment.</p> <p>The current width of Allum Lane is considered sufficient for the amount of traffic present as well as an additional access for a school. However, the access location and associated impact on the B5378 Allum Lane would need to be carefully considered in order to minimise the impact on the free flow of traffic along the road while also providing a suitable access arrangement for the school site.</p> <p>It is suggested that adequate pedestrian crossings are provided along Allum Lane and at suitable locations within the residential area to the east, in order to provide a safe and suitable route for pupils to access the school.</p> <p>The footway network along residential roads to the east and north-east of the site is generally considered suitable.</p> <p>Bus accessibility to the site from Borehamwood and Elstree is reasonable, with bus stops on the B5378 Allum Lane. Improved accessibility between the site and the local bus stops should be considered as part of proposals.</p> |   |



|  |  |
|--|--|
|  | <p>Due to the Covid-19 pandemic, traffic conditions at the time of writing this High-Level Assessment do not reflect former 'typical' traffic condition. Therefore, it is not possible to comment upon existing highway conditions in terms of congestion in the vicinity of the site. It is likely that any congestion issues occur at junction with London Road, which may cause school related traffic to use the network of residential roads near the school to avoid delays.</p> <p>It is recommended that safety across the mini-roundabout junction between the B5378 and Deacons Hill Road is reviewed, considering the potential increase in traffic and pedestrian movements related with the school development.</p> |
| <b>ENVIRONMENTAL IMPACT</b>  |  |
| <b>Landscape and visual impact</b>                                 | The site is relatively well enclosed from long distance views from all directions due to the topography and surrounding vegetation. There are short-distance private views of the site from the east.  |
| <b>Impact on residential amenities:</b>                            | Residential dwellings directly abut the site to the east. There is potential for harm to occur to residential amenity arising from loss of daylight/sunlight, outlook, noise and light overspill.  |
| <b>Ecology:</b>  | The majority of the site is in agricultural pasture use. The ecological value of the site is considered to be limited to the boundary vegetation which could provide habitats for bats, birds and small invertebrate and mammals. The large, wooded area to the south of the site is likely to be of high ecological value.  |
| <b>Noise sources</b>   | A recycling centre is situated directly west of the site.  |
| <b>Flood risk</b>  | Flood zone 1 – very low risk.  |
| <b>Surface water flooding</b>                                      | Most of the site is at very low risk, however there are bands of high risk to the south and south-west of the site.  |
| <b>Groundwater source protection area</b>                          | None.  |
| <b>Air quality</b>   | None.  |
| <b>Minerals</b>  | None.  |
| <b>Agricultural land quality</b>                                   | 3a/3b  |
| <b>Rights of way</b>   | Elstree and Borehamwood footpath 07 runs through the centre of the site.   |
| <b>EXISTING PLANNING AND DESIGNATION CONSTRAINTS</b>               |  |
| <b>Existing and emerging local plan site specific designations</b> | <p>Green Belt.</p> <p>Identified as site HEL393 in HELAA 2019 report.</p>  |
| <b>Heritage assets: archaeology</b>                                | Adjoins area of archaeological interest.   |



|  |   |
|--|---|
| <b>Designated heritage assets</b>  | Grade II Nicoll Farm on opposite side of Allum Lane |
| <b>Designated rural areas</b>  | None.   |
| <b>International, National and locally designated sites of importance for biodiversity and habitat sites</b> | None.   |

## SITE EVALUATION

### Positive site attributes:

1. The site is of optimal / sufficient size for 8fe.
2. The site is available.
3. The site has relatively gentle level changes and re-grading would be limited.
4. Vehicular access could potentially be achieved from Allum Lane with suitable mitigation/improvements.
5. Pedestrian/cycle access could potentially be achieved from Allum Lane with suitable mitigation/improvements.
6. The site lies adjacent/within 400m walking distance of bus stops and bus routes.
7. Site development would not be exposed to long distance views in the wider landscape.
8. The site has relatively small areas of vegetation that would require removal to accommodate a secondary school.
9. The site lies adjacent to the urban area of Borehamwood/Elstree.
10. There would be minor ecological impact [subject to further investigations].
11. The site is not located near any noise sources.
12. The site does not lie in a Minerals Consultation Area.
13. The site lies outside an AQMA.
14. The site is not in a designated rural area.
15. The site does not have any international, national or local wildlife, habitat or biodiversity designations.
16. The site does not have any local plan allocation.

### Negative site attributes:

1. The site is in more than one ownership.
2. There could be impacts on archaeology [subject to further investigations].
3. There would be impacts on preserved trees.
4. The site is at risk of surface water flooding [subject to further investigations].
5. The site lies in the Green Belt.
6. There could be impacts on designated heritage assets.
7. The site does have an HELAA allocation [HEL393].
8. The site has moderate-good grade agricultural land classification [if relevant].



9. The site is traversed by rights of way.

10. The site more than one landowner/is not in the ownership of HCC.

## SITE LAYOUT PRINCIPLES

A BB103 compliant 8fe secondary school site could be accommodated on this site:

### Option 1

1. Development principles plan 5309/372
2. Total site area: [16.00 ha]
3. Build zone: [3.97 ha]
4. Playing Field Zone: [6.57 ha]
5. Building footprint: [11,557 sqm]
6. Vehicular access/egress: [The Rise]
7. Pedestrian access: [The Rise / Allum Lane]

### Option 2

1. Development principles plan 5309/372
2. Total site area: [16.00 ha]
3. Build zone: [3.60 ha]
4. Playing Field Zone: [8.98 ha]
5. Building footprint: [11,557 sqm]
6. Vehicular access/egress: [Allum Lane]
7. Pedestrian access: [The Rise / Allum Lane]

## CONCLUSION

The site is located south of Allum Lane, Borehamwood (plan 5309/301/B). The existing use is agricultural pastureland. The site is in 3 ownerships. The site is an optimal size for an 8fe secondary school.

Although the site is undulating with a gentle slope upwards towards the centre of the site and downwards on either side to the east and west it is relatively enclosed, and the site is known to be available. There are two potential points of access from The Rise or Allum Lane which could potentially be used. The site was recommended for a highway appraisal.

The conclusions of the high-level transport appraisal were that in principle, it would appear that the road network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment. The current width of Allum Lane is considered sufficient for the amount of traffic present as well as an additional access for a school. However, the access location and associated impact on the B5378 Allum Lane would need to be carefully considered in order to minimise the impact on the free flow of traffic along the road while also providing a suitable access arrangement for the school site. It is suggested that adequate pedestrian crossings are provided along Allum Lane and at suitable locations within the residential area to the east, in order to provide a safe and suitable route for pupils to access the school. The footway network along residential roads to the east and north-east of the site is generally considered suitable. Bus accessibility to the site from Borehamwood and Elstree is reasonable, with bus stops on the B5378 Allum Lane. Improved



accessibility between the site and the local bus stops should be considered as part of proposals.

Due to the Covid-19 pandemic, traffic conditions at the time of writing do not reflect former 'typical' traffic condition. Therefore, it is not possible to comment upon existing highway conditions in terms of congestion in the vicinity of the site. It is likely that any congestion issues occur at junction with London Road, which may cause school related traffic to use the network of residential roads near the school to avoid delays. It is recommended that safety across the mini-roundabout junction between the B5378 and Deacons Hill Road is reviewed, considering the potential increase in traffic and pedestrian movements related with the school's development. The site was ranked 2/6 in terms of highways and access. The vehicular access to the site would likely need to be situated on Allum Lane. If the site was also used for residential purposes, the siting of the school development would need to ensure that access to the wider site is suitable for residential purposes.

Two development principles plans (5309/372 and 5309/373) have been prepared and are attached at Appendix 3. Plan 5309/372 shows the retention of the possible housing allocation (hatched) with a school building zone to the south accessed from The Rise and playing fields to the west of the site. The location of the school would necessitate the diversion of a footpath along the tree line boundary (as shown), locating the playing fields on significantly undulating land (particularly the farthest western parcel) requiring significant re-grading and the use of The Rise which, at this stage has been identified in the transport appraisal as a sub-optimal access solution. Overall, the site area for the school would be slightly sub-optimal being 10.54ha which is just below the 10.78ha requirement for an 8fe secondary school.

Plan 5309/373 shows the removal of the possible housing allocation with a school building zone to the north accessed from Allum Lane and the playing fields to the south of the school building zone. The location of the school would not necessarily require the diversion of the footpath if a secure line through the playing field could be established with the use of fencing. However, the footpath could be diverted if required along the tree line as shown on plan 5309/392. This site arrangement would not require the farthest western parcel of the site thus reducing potential re-grading requirements. This option proposes the use of Allum Lane which at this stage has been identified in the highway appraisal as the preferred access solution. There may be a requirement for a landscape buffer to manage the relationship between the building zone and adjoining residential dwellings on the eastern site boundary. Overall, the site area for the school would be 12.58ha which is above the 10.78ha requirement for an 8fe secondary school.


At this stage, given the constraints currently identified, the preferred land use option would be the development principles layout shown on plan 5309/373.

It is concluded that the site can be taken forward for comparative assessment with other sites.

Further site investigations are recommended comprising:

- Traffic condition survey (post Covid-19 levels)
- Noise Impact Assessment
- Air Quality Assessment
- Landscape and Visual Assessment
- High-level flood risk/drainage assessment
- Archaeological Desk Based Assessment





**SITE BOUNDARY**  
16.00ha

**OTHER POTENTIAL SITES**

## SOUTH WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH

Site identification: BORE06

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 370        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | JUNE 2020  | 1:2500 @A2 |

T: +44 (0) 1438 316 331  
planners@vincent-gorbing.co.uk  
vincent-gorbing.co.uk

Vincent and Gorbing Limited, Sterling Court  
Norton Road, Stevenage, Hertfordshire SG1 2JY

© Copyright Vincent and Gorbing Limited 2016.








**SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH**

Site identification: BORE07

| PROJECT NO | DRAWING NO | REV        |
|------------|------------|------------|
| 5309       | 371        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | JUNE 2020  | 1:2500 @A2 |







- SITE BOUNDARY  
16.00ha
- PROPOSED SCHOOL BOUNDARY  
10.54ha
- BUILDING ZONE  
3.89ha
- PLAYING FIELD ZONE  
6.65ha
- SITE ACCESS
- POTENTIAL RESIDENTIAL DEVELOPMENT AREA

## SOUTH WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH


Development principles: BORE06

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 372        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | SEPT 2020  | 1:2500 @A2 |

T: +44 (0) 1438 316 331  
planners@vincent-gorbing.co.uk  
vincent-gorbing.co.uk  
Vincent and Gorbing Limited, Sterling Court  
Norton Road, Stevenage, Hertfordshire SG1 2JY  
© Copyright Vincent and Gorbing Limited 2016.









## SOUTH -WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH: SHORTLISTED POTENTIAL SCHOOL SITE

### SITE DETAILS

|                                   |   |   |
|-----------------------------------|---|---|
| <b>Site Reference and address</b> | Borehamwood: Site BORE08<br>Land south of Barnet Lane, Borehamwood<br>Site identification plan: 5309/380 A<br>Aerial photograph: 5309/381 A<br>Development principles plan: [5309/382]  |   |
| <b>Site area</b>                  | 11.3 ha   |   |
| <b>Existing use/occupiers</b>     | Agricultural  |   |
| <b>Land ownership</b>             | HERTFORDSHIRE COUNTY COUNCIL of County Hall, Hertford SG13 8DE and of DX145781, Hertford 4  |   |
| <b>Site availability</b>          | Owned by HCC – available.   |   |
| <b>Brownfield Land Register</b>   | No.   |   |
| <b>Planning history</b>           | TP/99/0005 - Erection of 24 metre high mono pole telecommunications tower with 4 antennae, radio equipment cabin and fence enclosure together with 35m long access track – Refuse permission  |   |
| <b>Buildings</b>                  | None.   |   |
| <b>Adjoining uses</b>             | North:  | The north of the site is bounded by Barnet Lane and a roundabout connecting to Furzehill Road and Farriers Way. Beyond this are residential dwellings and to the north-east is a large supermarket. |
|                                   | East:   | To the east of the site is a caravan park, agricultural land and woodland.  |
|                                   | South:  | To the south of the site is agricultural land, beyond which is a large area of woodland.  |
|                                   | West:   | To the west are low density dwelling fronting onto Barnet Lane.   |
| <b>Topography</b>                 | The site is almost entirely level. There is a very gentle incline to the south-west.  |   |
| <b>Water courses</b>              | Google Maps shows a narrow watercourse around the perimeter of the adjacent caravan park.   |   |
| <b>Vegetation</b>                 | There is a hedgerow and tree belt bounding the site from Barnet Lane. A sporadic hedgerow/tree belt screens most of the caravan park from the site. There are a few singular trees dispersed within the central areas of the site. The area of the site to the south of the caravan park is |   |



separated from the northern part of the site by a mature hedgerow.

The central area of the site comprises long grassland.

## ACCESSIBILITY

|                                       |  |
|---------------------------------------|--|
| <b>Vehicular access</b>               | The is no existing vehicular access to the site. The site is bounded to the north by Barnet Lane, a principal A road with 40mph restrictions. Just over 100m to the east is the Barnet Bypass which connects to the A1(M).   |
| <b>Cycle access</b>                   | The pavement on the northern side of Barnet Lane, opposite the site, has a dedicated cycle lane, although this terminates after a short distance.  |
| <b>Pedestrian access</b>              | There is no pedestrian access to the site. There is a pavement along the northern side of Barnet Lane and a pavement leading to a bus stop on the southern side of the road, accessed via a pedestrian crossing point opposite the nearby supermarket.   |
| <b>Public transport</b>               | Stirling Court bus stop is located directly adjacent to the site and provides access to routes 107 (Edgeware to New Barnet via Borehamwood/Elstree) and 292 (Borehamwood – Edgeware).  |
| <b>High level transport appraisal</b> | <p>A high-level transport appraisal prepared by Stomor Civil Engineering Consultants concludes that, in principle, it would appear that the road network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment.</p> <p>Although the Highway Authority usually resists new accesses onto A roads, the A411 Barnet Lane to the west of Furzehill Road appears to be a suitable location for a school access to be established, provided an acceptable junction arrangement can be achieved.</p> <p>There may be potential for park and stride arrangements from nearby car parks associated with Morrisons and other commercial properties on Stirling Way, which would help to discourage travel by car and avoid provision of parent drop off facilities on site.</p> <p>The local footway and cycleway network appears to be generally good and suitable for school related movements. However, upgraded crossing facilities will be required, particularly on the A411 Barnet Lane.</p> <p>It is recommended that measures to manage traffic speed would be required in the vicinity of the school such as a reduction in speed limit to 30mph in the immediate vicinity of the site.</p> <p>Bus accessibility to the site is considered good, with bus stops adjacent to the site and within close proximity. Access between the site and the local bus stops should be considered as part of the proposals.</p> <p>Due to the Covid-19 pandemic, traffic conditions at the time of writing this High-Level appraisal do not reflect former 'typical' traffic condition. Therefore, it is not possible to comment upon existing highway conditions in terms of congestion in the vicinity of the site. It is likely that any congestion issues occur at junction with London Road, which may cause school traffic to use the adjacent network of residential roads to</p> |



|  |  |
|--|--|
|  | <p>avoid delays.</p> <p>It is recommended that safety on the eastbound approach to the A411 Barnet Lane and Furzehill Road is reviewed, as well as the safety of school related traffic on Stirling Corner.</p>                |
| <b>ENVIRONMENTAL IMPACT</b>  |  |
| <b>Landscape and visual impact</b>   | The site is not exposed to long distance views.  |
| <b>Impact on residential amenities:</b>  | Dwellings fronting onto Barnet Lane and occupiers of the adjacent caravan park may incur a loss of daylight, sunlight or outlook depending on where the school building is sited. There may also be light and noise overspill. |
| <b>Ecology:</b>  | The trees and hedgerows surrounding and within the site are likely to provide habitats for birds and potentially bats. The long grass on site may also provide habitat for lizards and other small invertebrates.              |
| <b>Noise sources</b>   | The site is in close proximity to the A1(M).   |
| <b>Flood risk</b>  | The eastern part of the site, adjacent to the caravan park is in Flood Zone 3.   |
| <b>Surface water flooding</b>  | There is a strip of low risk along the northern boundary of the site. To the east of the site, close to the caravan park, the site is at high risk of surface water flooding.  |
| <b>Groundwater source protection area</b>  | None.  |
| <b>Air quality</b>   | Part of the London Borough of Barnet AQMA.   |
| <b>Minerals</b>  | Sand and Gravel Belt.  |
| <b>Agricultural land quality</b>   | 3a/3b.   |
| <b>Rights of way</b>   | None known.  |
| <b>EXISTING PLANNING AND DESIGNATION CONSTRAINTS</b>   |  |
| <b>Existing and emerging local plan site specific designations</b>                                     | Green Belt.  |
| <b>Heritage assets: archaeology</b>  | Area of archaeological interest.   |
| <b>Designated heritage assets</b>  | None within close proximity.   |
| <b>Designated rural areas</b>  | None.  |
| <b>International, National and locally designated sites of importance for biodiversity and habitat</b> | None.  |



|  |  |
|--|--|
| sites  |  |
| <b>SITE EVALUATION</b>   |  |
| <p><b>Positive site attributes:</b></p> <ol style="list-style-type: none"> <li>1. The site is of optimal / sufficient size for 8fe.</li> <li>2. The site is in single ownership.</li> <li>3. The site is available.</li> <li>4. The site is flat and re-grading would be minimal.</li> <li>5. Vehicular access could be achieved from – A411 Barnet Lane with suitable mitigation/improvements.</li> <li>6. Pedestrian/cycle access could be achieved from – A411 Barnet Lane with suitable mitigation/improvements.</li> <li>7. The site lies adjacent/within 400m walking distance of bus stops and bus routes.</li> <li>8. Site development would not be exposed to long distance views in the wider landscape.</li> <li>9. The site lies adjacent to the urban area of Borehamwood.</li> <li>10. There would be no impacts on preserved trees.</li> <li>11. There would be minor ecological impact [subject to further investigations].</li> <li>12. There would be no impacts on designated heritage assets.</li> <li>13. The site is not in a designated rural area.</li> <li>14. The site does not have any international, national or local wildlife, habitat or biodiversity designations.</li> <li>15. The site does not have any local plan allocation.</li> <li>16. The site is not an identified HELAA site.</li> <li>17. The site is not traversed by rights of way.</li> <li>18. The site has a single landowner/is in the ownership of HCC.</li> </ol> |  |
| <p><b>Negative site attributes:</b></p> <ol style="list-style-type: none"> <li>1. The site is at risk of flooding [subject to further investigations].</li> <li>2. The site is located near noise sources.</li> <li>3. The site lies in the Green Belt.</li> <li>4. The site lies in an AQMA.</li> <li>5. The site lies in a Minerals Consultation Area.</li> <li>6. The site is in an Area of Archaeological Importance.</li> <li>7. The site has moderate-good grade agricultural land classification [if relevant].</li> <li>8. Relatively large areas of vegetation may have to be removed to accommodate development on the site.</li> </ol>  |  |
| <b>SITE LAYOUT PRINCIPLES</b>  |  |
| <p>A BB103 compliant 8fe secondary school site could be accommodated on this site:</p> <ol style="list-style-type: none"> <li>1. Development principles plan 5309/382</li> <li>2. Total site area: [11.00 ha]</li> </ol>   |  |



3. Build zone: [3.57 ha]
4. Playing Field zone: [7.43 ha]
5. Building footprint: [11,557 sqm]
6. Vehicular access/egress: [Barnet Lane]
7. Pedestrian access: [Barnet Lane]

## CONCLUSION

The site is located south of A411 (Barnet Lane), Borehamwood (plan 5309/381). The existing use is agricultural. The site is in 1 ownership, Hertfordshire County Council. The site is an optimal size for an 8fe secondary school. The site lies part in the administrative borough of Hertsmere and part in the administrative borough of Barnet. The site is almost entirely level. The site was recommended for a high-level transport appraisal.


The conclusions of the high-level transport appraisal were that: in principle, it would appear that the road network and potential for sustainable access to the site would be suitable for provision of an 8FE Secondary school, subject to a full review of transport impact and safety as part of a full Transport Assessment. Although the Highway Authority usually resists new accesses onto A roads, the A411 Barnet Lane to the west of Furzehill Road appears to be a suitable location for a school access to be established, provided an acceptable junction arrangement can be achieved. There may be potential for park and stride arrangements from nearby car parks associated with Morrisons and other commercial properties on Stirling Way, which would help to discourage travel by car and avoid provision of parent drop off facilities on site. The local footway and cycleway network appear to be generally good and suitable for school related movements. However, upgraded crossing facilities will be required, particularly on the A411 Barnet Lane. It is recommended that measures to manage traffic speed would be required in the vicinity of the school such as a reduction in speed limit to 30mph in the immediate vicinity of the site. Bus accessibility to the site is considered good, with bus stops adjacent to the site and within close proximity. Access between the site and the local bus stops should be considered as part of the proposals. Overall, the site was ranked 1/6 (receiving the top ranking) when compared with other sites.

A development principles plan (5309/380) has been prepared and is attached at Appendix 3. The plan shows the disposition of the building zone, playing fields and the optimal point of vehicular access to the site (based on highway appraisal conclusions). The highways appraisal identified 2 potential points of access from Barnet Lane to the east and west of the roundabout adjoining the site. The eastern point of access has been identified to allow for the building zone to be located away from the area of potential high-risk surface water flooding at the eastern part of the site. The playing fields may impact on a tree line running east west through the site but depending on layout the tree line may be retained. Some vegetation along the site frontage and scattered trees may require removal.

It is concluded that the site can be taken forward for comparative assessment with other sites. Further site investigations are recommended comprising:

- Traffic condition survey (post Covid-19 levels)
- Noise Impact Assessment
- Air Quality Assessment
- Landscape and Visual Assessment
- High-level flood risk/drainage assessment
- Archaeological Desk Based Assessment





**SITE BOUNDARY**  
11.00ha

**BORE 08**

REVISION A:  
Site boundary amendment  
HNA/21-09-2020

**SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH**

Site identification: BORE08

| PROJECT NO | DRAWING NO  | REV        |
|------------|-------------|------------|
| 5309       | 380         | A          |
| DRAWN      | DATE        | SCALE      |
| HNA        | AUGUST 2020 | 1:2500 @A2 |

T: +44 (0) 1438 316 331  
planners@vincent-gorbing.co.uk  
vincent-gorbing.co.uk  
Vincent and Gorbing Limited, Sterling Court  
Norton Road, Stevenage, Hertfordshire SG1 2JY  
© Copyright Vincent and Gorbing Limited 2016.







REVISION A:  
Site boundary amendment.  
HNA/21-09-2020

## SOUTH WEST HERTFORDSHIRE SECONDARY SCHOOL SITE SEARCH


Aerial photograph: BORE08

| PROJECT NO | DRAWING NO  | REV        |
|------------|-------------|------------|
| 5309       | 381         | A          |
| DRAWN      | DATE        | SCALE      |
| HNA        | AUGUST 2020 | 1:2500 @A2 |

T: +44 (0) 1438 316 331  
planners@vincent-gorbing.co.uk  
vincent-gorbing.co.uk  
Vincent and Gorbing Limited, Sterling Court  
Norton Road, Stevenage, Hertfordshire SG1 2JY  
© Copyright Vincent and Gorbing Limited 2016.







SITE BOUNDARY  
11.00ha

BUILDING ZONE  
3.57ha

PLAYING FIELD ZONE  
7.43ha

SITE ACCESS


**BORE 08**

**SOUTH WEST HERTFORDSHIRE  
SECONDARY SCHOOL  
SITE SEARCH**

Development principles: BORE08

|            |            |            |
|------------|------------|------------|
| PROJECT NO | DRAWING NO | REV        |
| 5309       | 382        |            |
| DRAWN      | DATE       | SCALE      |
| HNA        | SEPT 2020  | 1:2500 @A2 |





KEY

- SITE BOUNDARY
- FOOTPATH
- BRIDLEWAY
- UNCLASSIFIED COUNTRY ROAD
- BYWAY OPEN TO ALL TRAFFIC
- WATERCOURSE
- LONDON LOOP
- POTENTIAL ACCESS LOCATION

| Rev                                | Description | Date     | Drawn     | Checked | Apvd.    |
|------------------------------------|-------------|----------|-----------|---------|----------|
| Project                            |             |          |           |         |          |
| SOUTH WEST HERTS SECONDARY SCHOOLS |             |          |           |         |          |
| Drawing Description                |             |          |           |         |          |
| BOREHAMWOOD SITE 08                |             |          |           |         |          |
| Drawing Number                     | Scale       | Date     | Drawn     | Checked | Approved |
| ST-2995-06                         | 1:5000@A3   | 17.08.20 | JJN       | SJB     | NJM      |
| Client                             |             |          | Architect |         |          |



## APPENDIX 5



South West Hertfordshire Secondary School Site Search

**High Level Transport Appraisal – Borehamwood Site Rankings**

The table below shows the ranking of the sites according to the level of compliance with highway policy. These rankings of sites are based on a safe and suitable access, sustainable transport modes, and likely mitigation works required.

| Ranking | Site  | Safe and suitable vehicular access | Location and Sustainable transport modes | Anticipated Mitigation Works | Comments  |
|---------|---|------------------------------------|--|------------------------------|---|
| 1       | 8: Land to the south of Barnet Lane             |                                    |  |                              | Good access to sustainable transport facilities. Concerns over impact of additional traffic and crossings on existing congestion. |
| 2       | 7: Land to the west of Bishops Avenue           |                                    |  |                              | Good access to the site and local transport network. Possible constraint to the east of Deacons Hill Road.                        |
| 3       | 4: Land to the east of Green Street/Cowley Hill |                                    |  |                              | Good pedestrian and vehicular access to the site. Reasonable access to local transport network.                                   |
| 4       | 3: Land to the east of Green Street/Cowley Hill |                                    |  |                              | Good pedestrian and vehicular access to the site. Reasonable access to local transport network.                                   |
| 5       | 5: Land to the east of Green Street/Cowley Hill |                                    |  |                              | Sufficient access to the site. Reasonable access to the local transport network. Issues with parking on Green Street.             |
| 6       | 2: Land to the east of Well End Road            |                                    |  |                              | No Bus stop in the immediate vicinity of the site. Limited potential for footway/ cycleway improvements along desire line.        |

The above rankings are based on an initial desk based appraisal and are subject to further surveys and the detailed analysis of a Transport Assessment.



**Vincent and Gorbing**  
Sterling Court, Norton Road  
Stevenage, Hertfordshire SG1 2JY

T: +44 (0) 1438 316 331  
[vincent-gorbing.co.uk](http://vincent-gorbing.co.uk)

**Ruth Gray**, Associate Director  
[ruth.gray@vincent-gorbing.co.uk](mailto:ruth.gray@vincent-gorbing.co.uk)

